



STATE OF WEST VIRGINIA
DEPARTMENT OF MINES
OIL AND GAS DIVISION //

Quadrangle CENTERPOINT

Permit No. DOD-210

WELL RECORD

Oil or Gas Well DRY
(KIND)


Company S. Robert Wells
Address 115 North Potomac St.-Hagerstown, Md.
Farm Francis Marion Yeater Acres 193
Location (waters) Frank's Run
Well No. 1 Elev. 874'
District McClellan County Doddridge
The surface of tract is owned in fee by F. M. Yeater
RFD #2 - Smithfield Address W. Va.
Mineral rights are owned by Same
Address _____
Drilling commenced April 1, 1955
Drilling completed February 11, 1956
Date Shot 2/15/56 From 2060 To 2078'
With 40 qts.
Open Flow 4 /10ths Water in 2 Inch
/10ths Merc. in _____ Inch
Volume 98,000 Cu. Ft.
Rock Pressure 45 lbs. 16 hrs.
Oil 15 gal. bbls., 1st 24 hrs.
Fresh water none feet feet
Salt water _____ feet feet

Casing and Tubing	Used in Drilling	Left in Well	Packers
Size			
16			Kind of Packer
13	11'		
10	234'		Size of
8 1/4	1155'		
6 3/4	1915'		Depth set
5 3/16			
3			Perf. top
2			Perf. bottom
Liners Used			Perf. top
			Perf. bottom

CASING CEMENTED _____ SIZE _____ No. Ft. _____ Date _____

COAL WAS ENCOUNTERED AT _____ FEET _____ INCHES
_____ FEET _____ INCHES _____ FEET _____ INCHES
_____ FEET _____ INCHES _____ FEET _____ INCHES

Formation	Color	Hard or Soft	Top	Bottom	Oil, Gas or Water	Depth Found	Remarks
Soil			0	16			
Gravel			16	22			
Shale			22	45	3 bbls. water	16' to 22'	
Shale			45	55			
Shale			55	75	H. F. Water	45' to 55'	
Sand			75	85			
Shale			85	185			
Shale	Red		185	220			
Shale	blue		220	265			
Sandy Shells		Hard	265	320			
Blue Shale			320	353			
Lime			353	387			
Blue Shale			387	402			
Lime		Hard	402	460			
Blue Shale			460	497			
Lime		Hard	497	570			
Black Shale			570	580			
Lime		Hard	580	608			
Coal - Pittsburgh			608	612			
Shale			612	641			
Sand	White	Hard	641	658			
Gray Shale			658	718			
Sand	White	Hard	718	738			
Pink Shale			738	780			
Gray Shale			780	792			
Sand	White	Hard	792	802			
Gray Shale			802	835			
Red Shale			835	860			
Gray Shale			860	902			
Red Shale			902	950			
Blue Shale			950	963			
Sand	White	Hard	963	1040			
Gray Shale			1040	1155			
Sand	White	Med.	1155	1179			
Blue Shale			1179	1195			
Sand	White	Hard	1195	1260			
Gray Shale			1260	1330			
Sand		Hard	1330	1365			
Shale	Dark G.	Soft	1365	1415	(OVER)		



Formation	Color	Hard or Soft	Top	Bottom	Oil, Gas or Water	Depth Found	Remarks
Sand	White	Hard	1415	1474			
Blue Shale			1474	1515			
Sand	White	Hard	1515	1590			
Shale - Gray		Med	1590	1615			
Sand	White	Hard	1615	1631			
Black Shale			1631	1760			
Red Shale			1760	1855			
Black Shale			1855	1912			
Lime		Hard	1912	1979			
Sand	White	Hard	1979	2030	Gas 1980'		
Blue Shale			2030	2040			
Sand - Gray		Hard	2040	2146	Show of oil	2060 to 2077'	
Shale	Dark G.	Med	2146	2200	Salt water with oil pay	from 2060'-77'	
Total Depth				2200'	Filled up to 100 feet		

Date _____, 19____

APPROVED _____, Owner

By _____