

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: ROBINSON H. G. Operator Well No.: 3

LOCATION: Elevation: 1134' Quadrangle: NEW MILTON
District: NEW MILTON County: DODDRIDGE
Latitude: 2680' Feet South of 39 Deg. 15 Min. 00 Sec.
Longitude: 700' Feet West of 80 Deg. 40 Min. 00 Sec.

Well Type: OIL _____ GAS X

Company DIVERSIFIED PRODUCTION LLC Coal Operator BRYAN R. ROBINSON **RECEIVED**
414 SUMMER STREET or Owner 23221 JENIFER COURT Office of Oil and Gas
CHARLESTON WV 25301 LEONARDTOWN, MD 20650

Agent JEFF MAST Coal Operator NO DECLARATION **APR 04 2022**
or Owner _____

Permit Issued Date 09/21/21 WV Department of Environmental Protection

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of JACKSON ss:


MELVIN MYERS and MICHAEL PROCTOR being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 6TH day of DECEMBER, 2021, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
35 SACKS OF C1A CEMENT	2263'	1975'	2080' OF 2 3/8 TUBING	
30 SACKS OF C1A CEMENT	1737'	1590'	2060' OF 5/8" RODS	2298' OF 5 3/16" CASING
47 SACKS OF C1A CEMENT	1323'	1223'		1640' OF 6 5/8" CASING
47 SACKS OF C1A CEMENT	1029'	929'		1273' OF 8 1/4" CASING
150 SACKS OF C1A CEMENT	192'	19'		142' OF 10" CASING
9 SACKS OF C1A CEMENT	19'	SURFACE		16' OF 13 CASING
6 1/2 OGL SPACERS BETWEEN PLUGS				

Description of monument: 7" CSG WITH API # 36" ABOVE GROUND and that the work of plugging and filling said well was completed on the 10TH day of DECEMBER, 2021.

And further deponents saith not.

[Signatures]



Sworn and subscribe before me this 24th day of January, 2022

My commission expires: 1/22/2025

[Signature]
Notary Public

Affidavit reviewed by the Office of Oil and Gas:

[Signature] Title: O&G Inspector