

WR-38  
Rev. 5/08

API# 47-017-00759

STATE OF WEST VIRGINIA  
DEPARTMENT OF ENVIRONMENTAL PROTECTION  
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: JOHNSON, ARCHIBALD Operator Well No.: 2

LOCATION: Elevation: 1136' Quadrangle: NEW MILTON  
District: NEW MILTON County: DODDRIDGE  
Latitude: 1940' Feet South of 39 Deg. 15 Min. 00 Sec.  
Longitude: 1240' Feet West of 80 Deg. 40 Min. 00 Sec.

Well Type: OIL \_\_\_\_\_ GAS X

Company DIVERSIFIED PRODUCTION LLC  
414 SUMMER STREET  
CHARLESTON WV 25301

Coal Operator BARBARA BOWMAN  
or Owner 1400 EOFF STREET  
WHEELING, WV 26003

Agent JEFF MAST  
Permit Issued Date 11/29/21

Coal Operator NO DECLARATION  
or Owner \_\_\_\_\_

RECEIVED  
Office of Oil and Gas

APR 04 2022

WV Department of  
Environmental Protection

AFFIDAVIT

STATE OF WEST VIRGINIA,  
County of JACKSON ss:

MELVIN MYERS and MICHAEL PROCTOR being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 10th day of DECEMBER, 2021, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
30 SACKS OF C1A CEMENT	2235'	2026'		
49 SACKS OF C1A CEMENT	1371'	1271'		
49 SACKS OF C1A CEMENT	1127'	1027'		1755' OF 4" CASING
40 SACKS OF C1A CEMENT	550'	450'	498' OF 4" CASING	2167' OF 6 5/8" CASING
49 SACKS OF C1A CEMENT	277'	177'		1321' OF 8 1/4" CASING
104 SACKS OF C1A CEMENT	100'	SURFACE		227' OF 10" CASING
6X CEL SPACERS BETWEEN PLUGS				14' OF 16" CASING


Description of monument: 7" CSG WITH API # 36" ABOVE GROUND and that the work of plugging and filling said well was completed on the 15TH day of DECEMBER, 2021.

And further deponents saith not.

Sworn and subscribe before me this 24th day of January, 2022

My commission expires: \_\_\_\_\_

Andria L. Wilson  
Notary Public



Affidavit reviewed by the Office of Oil and Gas: S. D. Wilson

Title: OOG Inspector

04/15/2022