



STATE OF WEST VIRGINIA
DEPARTMENT OF MINES
OIL AND GAS DIVISION 4

Quadrangle West Union

Permit No. Dod-846

WELL RECORD

Oil or Gas Well Oil
(KIND)

Company Dominion Oil & Gas Company
Address 208 Nelson Building
Farm E. Spurgeon et. al. Acres 82
Location (waters) _____
Well No. One Elev. 1038'
District Central County Doddridge
The surface of tract is owned in fee by E. Spurgeon et al
Address Greenwood, W.Va.
Mineral rights are owned by E. Spurgeon et al
Address Greenwood, W.Va.
Drilling commenced 8-3-62
Drilling completed 9-5-62
Date Shot _____ From _____ To _____
With _____
Open Flow _____ /10ths Water in _____ Inch
_____ /10ths Merc. in _____ Inch
Volume _____ Cu. Ft.
Rock Pressure _____ lbs. _____ hrs.
Oil Show _____ bbls., 1st 24 hrs.
WELL ACIDIZED _____


Casing and Tubing	Used in Drilling	Left in Well	Packers
Size			Kind of Packer _____
16			
18	20'		
10	250'		Size of _____
8 3/4	130'		
6 3/4			Depth set _____
5 1/2	2119'	2119'	
3			Perf. top <u>2071 1/2</u>
2			Perf. bottom <u>2073 1/2</u>
Liners Used			Perf. top _____
			Perf. bottom _____

CASING CEMENTED 5 1/2" SIZE 350 No. Ft. 11-14-62 Date
10 sks. Bentonite, 60 sks. Hi F (API
Western Co. Type C)
COAL WAS ENCOUNTERED AT _____ FEET _____ INCHES
_____ FEET _____ INCHES
_____ FEET _____ INCHES

WELL FRACTURED 1-5-63 with 700 BBLs crude, 20,000# 20-40; 9,000# 10-20; 250 gals. mud acid.

RESULT AFTER TREATMENT 20 B.O.P.D.
ROCK PRESSURE AFTER TREATMENT _____
Fresh Water 90' Feet Salt Water 1190' - 1/2 B.P.H. Feet 1575'-EXH.

Formation	Color	Hard or Soft	Top	Bottom	Oil, Gas or Water	Depth	Remarks
Red Rock		S	0	150	Water	90'	
Slate		S	150	165			
Red Rock		S	165	225			
Slate		S	225	265			
Red Rock		S	265	420			
Slate		S	420	450			
Red Rock		S	450	570			
Sand		H	570	630			
Slate		S	630	660			
Red Rock		S	660	685			
SL & SH		S	685	710			
Lime		H	710	740			
SL & SH		S	740	850			
Red Rock		S	850	1010			
Slate		S	1010	1050			
Red Rock		S	1050	1145			
Slate		S	1145	1185			
Sand		H	1185	1365			
SL & SH		S	1365	1505			
Sand		H	1505	1600			
SL & SH		S	1600	1685			
Sand		S	1685	1710			
SL & SH		S	1710	1740			



Formation	Color	Hard or Soft	Top <i>4</i>	Bottom	Oil, Gas or Water	Depth Found	Remarks
Sand		H	1740	1795			
SL & Sh		S	1795	1835			
Slate		S	1835	1907			
Maxon		H	1907	1923			
Slate		S	1923	1930			
Little Lime		H	~1930	1959			
Blue Monday		S	1959	1974			
Big Lime		H	~1974	2034			
Keener		H	2034	2055			
Injun		S	2055	2104			
Slate		S	2104	2119			
			TD	2119'			

Date....., 19.....

APPROVED....., Owner

By.....
(Title)