



STATE OF WEST VIRGINIA
DEPARTMENT OF MINES
OIL AND GAS DIVISION

Rotary
Spudder
Cable Tools
Storage Gas sho
Oil or Gas Well oil we
(KIND)

Quadrangle Vadis

Permit No. DOD - 983

WELL RECORD

Company Southern Triangle Oil Company
Address Box 230, Mt. Carmel, Illinois
Farm B. Detterman Acres 93
Location (waters) Brushy Fork
Well No. 2 Elev. 1114
District New Milton County Doddridge
The surface of tract is owned in fee by W. V. Schulte
Address New Milton, W. Va.
Mineral rights are owned by W. V. Schulte
Address New Milton, W. Va.

Casing and Tubing	Used in Drilling	Left in Well	Packers
Size			Kind of Packer
16			
13			
10			Size of
8 1/4	260	260	
6 5/8			Depth set
5 3/16	2402	2402	
3			Perf. top
2			Perf. bottom
Liners Used			Perf. top
			Perf. bottom

Drilling commenced 6-5-63
Drilling completed 6-29-63
Date Shot _____ From _____ To _____
With _____
Open Flow /10ths Water in _____ Inch
/10ths Merc. in _____ Inch
Volume 100,000 Cu. Ft.
Rock Pressure 750 lbs. 24 hrs.
Oil (50) bbls., 1st 24 hrs.
WELL ACIDIZED NO
WELL FRACTURED NO


CASING CEMENTED SIZE 5 1/2 No. Ft. 2402 Da
100 sks. cement-Dowell
COAL WAS ENCOUNTERED AT 0 FEET 0 INCHES
_____ FEET _____ INCHES FEET _____ INCHES
_____ FEET _____ INCHES FEET _____ INCHES

RESULT AFTER TREATMENT

ROCK PRESSURE AFTER TREATMENT

Fresh Water none Feet Salt Water none Feet

Formation	Color	Hard or Soft	Top	Bottom	Oil, Gas or Water	Depth	Remarks
soil	yellow	soft	0	13			
shly sand	tan	soft	13	74			
shale	grey	soft	74	212			
shly sand	grey	soft	213	341			
shale	grey	soft	341	314			
sand	white	soft	414	472			
shale	grey	soft	472	608			
shly sand	grey	soft	608	797			
sand	white	soft	797	921			
shale	grey	soft	921	1154			
shly sand	grey	soft	1154	1215			
shale	grey	soft	1215	1349			
sand, shly	grey	soft	1349	1408			
shale	grey	soft	1408	1461			
sand	white	hard	1461	1580			
shale	grey	soft	1580	1731			1st salt sand
shly sand	grey	hard	1731	1814			
shale	green	soft	1814	1904			
sand	white	hard	1904	1963			
shale &							
shly sand	grey	soft	1963	2260			
Little Lime	brown	hard	2260	2273			
shale	green	soft	2273	2882			
Blue Monday	white	hard	2286	2332			
Big Lime	brown	hard	2332	2358			
sandy lime	grey	hard	2358	2402			
sand	white	soft	2402	(over) 2423			



1st salt sand