

Derivation of Elevation: - U.S.G.S.  
 B.M. on bridge across Indian Fork of  
 Brushy Fork, marked "7-JEA". elev: 850'

I, the undersigned, hereby certify that this map is correct to the best of my knowledge and belief and that I am the information required by paragraph 6 of the rules and regulations of the oil and gas section of the mining laws of West Virginia.

*Walter J. [Signature]*  
 1963

New Location   
 Drill Deeper   
 Abandonment

Error of Closure: - Less than 1" : 200'

Company	<b>CREST OIL CO.</b>
Address	Box 57, Alton, Illinois
Farm	Henry A'House Hairs 100 ac.
Tract	Acres 50 Lease No.
Well (Farm) No.	Three Serial No.
Elevation (Spirit Level)	1217
Quadrangle	Vadis Wc
County	Doddridge District New Milton
Engineer	<i>Walter J. [Signature]</i>
Engineer's Registration No.	1227
File No.	Drawing No.
Date	June 24, 1963 Scale 1" = 300' = 495'

STATE OF WEST VIRGINIA  
 DEPARTMENT OF MINES  
 OIL AND GAS DIVISION  
 CHARLESTON

WELL LOCATION MAP  
 FILE NO. Dod-1024

+ Denotes location of well on United States Topographic Maps, scale 1 to 62,500, latitude and longitude lines being represented by border lines as shown.

- Denotes one inch spaces on border line of original tracing.



STATE OF WEST VIRGINIA  
DEPARTMENT OF MINES  
OIL AND GAS DIVISION 5

Rotary   
Spudder,   
Cable Tools   
Storage

Quadrangle Vadis  
Permit No. DCD-1024

WELL RECORD

Oil or Gas Well Oil  
(KIND)

Company Crest Oil Company  
Address P. O. Box 57 Alton, Illinois  
Farm Henry Ahouse Acres So. 50  
Location (waters) Brushy Fork  
Well No. Three (3) Elev. 1217 G.L.  
District New Milton County Doddridge  
The surface of tract is owned in fee by O. C. Haught  
Address W. Union, W. Va.  
Mineral rights are owned by O. C. Haught et al  
Address W. Union, W. Va.  
Drilling commenced 1/26/64  
Drilling completed 3/9/64  
Date Shot \_\_\_\_\_ From \_\_\_\_\_ To \_\_\_\_\_  
With \_\_\_\_\_  
Open Flow \_\_\_\_\_ /10ths Water in \_\_\_\_\_ Inch  
\_\_\_\_\_ /10ths Merc. in \_\_\_\_\_ Inch  
Volume \_\_\_\_\_ Cu. Ft.  
Rock Pressure 900 lbs. 24 hrs.  
Oil 100 bbls., 1st 24 hrs.  
WELL ACIDIZED No  
WELL FRACTURED No

Casing and Tubing	Used in Drilling	Left in Well	Packers
Size			Kind of Packer
16			
13			Size of
10			
8 1/4			Depth set
6 5/8	50°	50°	
<del>XXXX</del> 4-1/2		2379°	Perf. top
3			Perf. bottom
2			Perf. top
Liners Used			Perf. bottom

CASING CEMENTED 4 1/2 SIZE 2379 No. Ft. 3/9/64 Date  
with 50 sks, float show, 3 centralizers, rotary  
COAL WAS ENCOUNTERED AT \_\_\_\_\_ FEET \_\_\_\_\_ INCHES  
\_\_\_\_\_ FEET \_\_\_\_\_ INCHES \_\_\_\_\_ FEET \_\_\_\_\_ INCHES  
\_\_\_\_\_ FEET \_\_\_\_\_ INCHES \_\_\_\_\_ FEET \_\_\_\_\_ INCHES

RESULT AFTER TREATMENT


ROCK PRESSURE AFTER TREATMENT

Fresh Water No Feet \_\_\_\_\_ Salt Water No Feet \_\_\_\_\_

Formation	Color	Hard or Soft	Top	Bottom	Oil, Gas or Water	Depth	Remarks
Shale			220	430			
Sd & Sh			430	610			
Sd & Sh			610	650			
Sd. & Sh			650	740			
Sd. & Sh			740	850			
Sd. & Sh			850	1100			
Sh & Sd			1100	1115			
Sh & Sd			1115	1250			
Sh & Sd			1250	1385			
Sand			1385	1430			
Sand			1430	1490			
Sand			1490	1580			
Sand			1580	1590			
Limey Sd			1590	1615			
Limey Sd			1615	1670			
Limey Sd.			1670	1720			
Limey Sand			1720	1760			
Limey Sd.			1760	1768			
Sd & Sh			1768	1820			
Sd & Sh			1820	1848			
Sd & Sh			1848	1860			
Sd & Sh			1860	1960			
Sd & Sh			1960	2050			
Lm & Sh			2050	2070			
Sh & Lm			2070	2125			
Sh & Lm			2125	2205			
Sh & Lm			2205	2225			



Formation	Color	Hard or Soft	Top 5	Bottom	Oil, Gas or Water	Depth Found	Remarks
Sh & Lm			2225	2260			
Lime			2260	2300			
Lime			2300	2307			
Lime			2307	2319			
Lime			2319	2325			
Big Lime			2325	2329			
Big Lime			2329	2355			
Limey Sd			2355	2379			
TD			2379				



Date May 5, 1964

APPROVED Crest Oil Company, Owner

By C. F. Swain

(Title)

C. F. Swain, Owner