

FILE NO. _____
 DRAWING NO. _____
 SCALE 1" = 500'
 MINIMUM DEGREE OF ACCURACY 1 IN 200
 PROVEN SOURCE OF ELEVATION BM PLEASANT VALLEY CHURCH 818'

I THE UNDERSIGNED, HEREBY CERTIFY THAT THIS PLAT IS CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF AND SHOWS ALL THE INFORMATION REQUIRED BY LAW AND THE REGULATIONS ISSUED AND PRESCRIBED BY THE DEPARTMENT OF MINES
 (SIGNED) David L. Mitchell
 R.P.E. _____ L.L.S. 873

PLACE SEAL HERE

WEST VIRGINIA
 DIVISION OF ENVIRONMENTAL PROTECTION
 OFFICE OF OIL AND GAS
 #10 McJUNKIN ROAD
 NITRO, WEST VIRGINIA 25143-2506
 (7-87)



DATE 11/28/89, 19____
 OPERATOR'S WELL NO. 4025
 API WELL NO. 47-017-02031 P
 STATE COUNTY PERMIT

was 017 71742 #

WELL TYPE: OIL ___ GAS X LIQUID INJECTION ___ WASTE DISPOSAL ___
 (IF "GAS,") PRODUCTION X STORAGE ___ DEEP ___ SHALLOW ___
 LOCATION: ELEVATION 958' WATER SHED BEAR FORK
 DISTRICT COVE COUNTY DODDRIDGE
 QUADRANGLE AUBURN/HOLBROOK SE 56-2!
 SURFACE OWNER BRUCE D. & GLADYS L. ROTH ACREAGE 141
 OIL & GAS ROYALTY OWNER JOHN A. GRAY ET AL LEASE ACREAGE 142
 LEASE NO. 6122
 PROPOSED WORK: DRILL ___ CONVERT ___ DRILL DEEPER ___ REDRILL ___ FRACTURE OR STIMULATE ___ PLUG OFF OLD FORMATION ___ PERFORATE NEW FORMATION ___ OTHER PHYSICAL CHANGE IN WELL (SPECIFY) _____
 PLUG AND ABANDON X CLEAN OUT AND REPLUG ___
 TARGET FORMATION BIG INJUN ESTIMATED DEPTH 1923' (T.D.)
 WELL OPERATOR EQUITRANS DESIGNATED AGENT BILL HOSTUTLER
 ADDRESS 4955 STEUBENVILLE PIKE ADDRESS P.O. BOX 1550
PITTSBURGH, PA. 15205 CLARKSBURG, WV 26301

Plugging the 1929 well drilled in 1912

JUN 13 1997

STATE OF WEST VIRGINIA
DIVISION OF ENVIRONMENTAL PROTECTION
SECTION OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: ROTH, BRUCE & GLADYS Operator Well No.: SPURGEON 4025

LOCATION: Elevation: 958.00 Quadrangle: AUBURN
District: COVE County: DODDRIDGE
Latitude: 1870 Feet South of 39 Deg. 7 Min. 30 Sec.
Longitude 11130 Feet West of 80 Deg. 45 Min. 0 Sec.

Well Type: OIL X GAS _____


Company: EQUITRANS L P
420 BOULEVARD OF THE ALLIES
PITTSBURGH PA 15275

Coal Operator
or Owner _____

Agent: WILLIAM HOSTUTLER

Coal Operator
or Owner _____

Permit Issued: 06/17/97



AFFIDAVIT

STATE OF WEST VIRGINIA,
County of DODDRIDGE ss:

LYLE D PERKINS and DONALD E HARRISON being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well, and MIKE UNDERWOOD Oil and Gas Inspector representing the Director, say that said work was commenced on the 11th day of May, 1998, and that the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED		LEFT
Gel	1923	1850	3 1/2	1855	0
Cement	1850	1750	6 5/8	960	880
		(tagged cmt	1500)		
Gel	1750	980	8 1/4	510	408
Cement	980	580	10	307	0
Gel	580	380			
Cement	380	280			
Gel	280	100			
Cement	100	surface			

[Signature] 6/13/98


Description of monument: 1 joint 8" csg extending 30" above surface and that the work of plugging and filling said well was completed on the 15th day of May, 1998.

And further deponents saith not.

Sworn and subscribe before me this 15th day of May, 1998
My commission expires: June 7, 2000

[Signature]
[Signature]
[Signature]
Notary Public

D000 2031-P



Oil and Gas Inspector: _____

JUN 13 1998