

STATE OF WEST VIRGINIA
DIVISION OF ENVIRONMENTAL PROTECTION
SECTION OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Smith, J.B. 4957 (604957) Operator Well No.: 604957
 LOCATION: Elevation: ? Quadrangle: Smithburg 7.5'
 District: West Union County: Doddridge
 Latitude: Feet South of 00 Deg. 00 Min. 00 Sec.
 Longitude: Feet West of 00 Deg. 00 Min. 00 Sec.

Well Type: OIL _____ GAS XXXX

Company: Paul Amos Smith Coal Operator None
140 Belvue or owner _____
Los Catos, CA 95032 _____

Agent: David Scranage
Route 2 Box 11
Lost Creek, WV 26385

Coal Lessee: None
 With declaration _____

Permit Issued Date: _____

AFFIDAVIT

STATE OF WEST VIRGINIA,
 County of Doddridge ss:


Jacob Snider and Jackie Carpenter being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well, and David Scranage Oil and Gas Inspector representing the Director, say that said work was commenced on the 4th day of January 2011 and that the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Cement	1995'	1870'	3" 1995'	756'
Cement	1850'	1660'		
Cement	1555'	1450'	7" 1232'	688'
Cement	1430'	1330'		
Cement	1280'	1180'	8 " 146'	666'
Cement	1064'	962'		
Cement	695'	595'	10" 108'	237'
Cement	792'	350'		
Cement	352'	295'		
Cement	250'	130'		
Cement	137'	0'		
6% Gel between each plug				
Shot 3" @ 1995'; Free; Shot 7" @ 1791'; 3 times; 1568'; 2 times; 1381'; 2 times; 1232'; 2 times; Free; Shot 8" @ 644'; 2 times; 442'; 2 times; 406'; 2 times; 346'; 2 times; Free; Shot 10" @ 206'; 2 times; 108'; 2 times; Free; Tagged plug @ 1850'; 1430'; 1160'; 352'; 292'; 137';				

Description of monument: 7 inch casing - 8 feet long with API # welded on it and that the work of plugging and filling said well was completed on the 27th day of January, 2011.

And further deponents saith not.

Sworn and subscribe before me this 2nd day of September, 2011



Sandra L. Messer
 Notary Public

David K. Scranage Title: Inspector

RECEIVED
 Office of Oil & Gas
 NOV 23 2011
 WV Department of Environmental Protection