

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: W. T. Snyder Operator Well No.: 604968 (W T Snyder #4968)

LOCATION: Elevation: 1058 Quadrangle: Oxford 7.5
District: South West County: Doddridge
Latitude: 39.147601 Feet South of _____ Deg. _____ Min. _____ Sec.
Longitude: -80.812657 Feet West of _____ Deg. _____ Min. _____ Sec.

Well Type: OIL _____ GAS X

Company EQT Production Co.
120 Professional Place
Bridgeport ~, WV 26330

Coal Operator Donald E. & Barbara H. Osborn
or Owner 29773 Chilcutt Rd
Easton, MD 21301-8611

Agent Rex C Ray
Permit Issued Date 03/16/2015

Coal Operator _____
or Owner _____

Received
SEP 17 2015

AFFIDAVIT

Office of Oil and Gas
WV Dept. of Environmental Protection

STATE OF WEST VIRGINIA,
County of Jackson ss:

Jacob Snider and Jack Carpenter being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 6th day of July, 2015, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Cement	1865'	1720'	10" 0	338'
Cement	1865'	1721'	8" 204'	798'
Cement	1655'	1580'	7" 1043	588'
Cement	1538'	1438'	5 1/2" 1647	124'
Cement	1380'	1280'	6 % Gel between all plugs	Tagged 1655', 1572', 1262', 880', 150'
Cement	1095'	900'	Cement from 390' To 290, Cement from 250' to 150	Cut Pipe 7" @ 1488', 1330', 1043', free; 5" @ 604', 343', 204', free
Cement	650'	550'	Cement from 150' to "0" Zero	5 1/2" @ 1647', free; 10" @ 98', tried to back off

Description of monument: 7" x 6' Long with API number welded on it and that the work of plugging and filling said well was completed on the 30th day of July, 2015.


And further deponents saith not.

Jacob Snider
Jack Carpenter

Sworn and subscribe before me this 3rd day of August, 2015

My commission expires: June 3, 2020

Mildred L. Casto
Notary Public



Affidavit reviewed by the Office of Oil and Gas: Douglas Nember Title: Oil & Gas Inspector 9/18/2015