

RECEIVED
WV Division of
Environmental Protection

017-4258

FORM WW-2B

Page ___ of ___

STATE OF WEST VIRGINIA
DIVISION OF ENVIRONMENTAL PROTECTION, OFFICE OF OIL AND GAS
WELL WORK PERMIT APPLICATION

1) Well Operator 45 of KEY OIL COMPANY 25655 1 671

2) Operator's Well Number: THOMAS #2 3) Elevation: 1260'

Well type: (a) Oil X / or Gas X /
(b) If Gas: Production X / Underground Storage /
Deep / / Shallow X /

Damaged 04/24/96
Expired 04/24/98

21863

Proposed Target Formation(s): ALEXANDER⁴³⁵

Proposed Total Depth: 5600 feet

Approximate fresh water strata depths: 100'

8) Approximate salt water depths: -0-

9) Approximate coal seam depths: N/A

10) Does land contain coal seams tributary to active mine? Yes / No X /

11) Proposed Well Work: DRILL, STIMULATE, PRODUCE
New Well

12)

CASING AND TUBING PROGRAM

TYPE	SIZE	GRADE	WEIGHT per ft.	FOOTAGE	LEFT IN well	CEMENT
Conductor						
Fresh Water	11 3/4	ERW	42	132	132	308918-11.3 70 SKS. TO SURFACE
Coal						308918-11.22
Intermediate	8 5/8	ERW	23	2240	2240	590 SKS. TO SURFACE
Production	4 1/2	J-55	10.5	5500	5500	350 SKS.
Tubing	1.5					308918-11.1
Liners						

PACKERS : Kind _____
Sizes _____
Depths set _____

For Office of Oil and Gas Use Only
Fee(s) paid: 1 Well Work Permit 1 Reclamation Fund 1 WPCP
Plat 1 WW-9 1 WW-2B 1 Bond 1 Agent 1
(Type)

RECEIVED
WV Division of
Environmental Protection

APR 22 1998

Permitting 3)
Office of Oil & Gas

Date: APRIL 17, 1996
Operator's well number
THOMAS #2
API Well No: 47 - 017 - 4258
State - County - Permit

STATE OF WEST VIRGINIA
DEPARTMENT OF ENERGY, DIVISION OF OIL AND GAS

NOTICE AND APPLICATION FOR A WELL WORK PERMIT

4) Surface Owner(s) to be served:

(a) Name PAUL DOTSON
Address RT. 1 BOX 232
WEST UNION, WV 26456

(b) Name _____
Address _____

(c) Name _____
Address _____

6) Inspector MIKE UNDERWOOD
Address RT. 2 BOX 135
SALEM, WV 26426
Telephone (304) - 782-1043

5) (a) Coal Operator:
Name NONE
Address _____

(b) Coal Owner(s) with Declaration
Name _____
Address _____

Name _____
Address _____

(c) Coal Lessee with Declaration
Name _____
Address _____

TO THE PERSON(S) NAMED ABOVE TAKE NOTICE THAT:

Included is the lease or leases or other continuing contract or contracts by which I hold the right to extract oil and gas OR

Included is the information required by Chapter 22B, Article 1, Section 8(d) of the Code of West Virginia (see page 2)

I certify that as required under Chapter 22B of the West Virginia Code I have served copies of this notice and application, a location plat, and accompanying documents pages 1 through _____ on the above named parties, by:
 Personal Service (Affidavit attached)

Certified Mail (Postmarked postal receipt attached)

Publication (Notice of Publication attached)

I have read and understand Chapter 22B and 38 CSR 11-18, and I agree to the terms and conditions of any permit issued under this application.

I certify under penalty of law that I have personally examined and am familiar with the information submitted on this application form and all attachments, and that based on my inquiry of those individuals immediately responsible for obtaining the information, I believe that the information is true, accurate, and complete.

I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment.

Weld Operator
BY: [Signature]
Its: PRÉSIDENT
Address 22 GARTON PLAZA
WESTON, WV 26452
Telephone 304-269-7102

Subscribed and sworn before me this 17th day of APRIL, 1996

My commission expires MARCH 24, 2003



OFFICIAL SEAL NOTARY PUBLIC
STATE OF WEST VIRGINIA
KAREN COOK
ROUTE 2, BOX 1
JANE LEW, WV 26378
Notary Public

JUL 01 1996

FORM WR-38 STATE OF WEST VIRGINIA
 (Affidavit of Plugging) **Office of Oil and Gas** AND GAS WELLS DIVISION
 Permitting DEPARTMENT OF ENERGY

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

None	Key Oil Company
Coal Operator or Owner	Name of Well Operator
Address	22 Garton Plaza, Weston, WV 26452
Coal Operator or Owner	Complete Address
Address	Thomas #2 June 17 19 96
Paul Dotson	WELL AND LOCATION
Lease or Property Owner	Central District
Rt. 1 Box 232, West Union, WV 26456	Doddridge County
Address	WELL NO. 47-017-4258P

STATE INSPECTOR SUPERVISING PLUGGING Mike Underwood gave verbal permission to plug this well on 6-17-96 and was present during plugging.
 AFFIDAVIT

STATE OF WEST VIRGINIA,

County of Lewis ss:

Bobby Mitchell and Tim Skinner
 being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by Key Oil Company, well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 17th day of June, 19 96, and that the well was plugged and filled in the following manner:


Sand or Zone Record	Filling Material	Plugs Used Size & Kind	Casing	
			CSG PULLED/LEFT IN	CSG 5/8"
Formation				
Total depth reached was 3750'.		1306' of 8 5/8" was cemented to surface.	0	1306' 8 5/8"
Drill bit and collars became stuck at 1981'.				
3750' - 1981'	Gel			
1981' - 1400'	Cement	55 sks., Class "A"		
Cut drill pipe off at 1372'.				
1372' - 1172'	Cement	50 sks., Class "A"		1372' 609'
1172' - 100'	Gel			
100' to surface	Cement	50 sks., Class "A"		
Coal Seams				
(Name) None		Description of Monument		
(Name)		30" monument with API# 47-017-4258P		
(Name)		inscribed.		
(Name)				

and that the work of plugging and filling said well was completed on the 17th day of June, 1996.

And further deponents saith not.

Sworn to and subscribed before me this 25th day of June, 19 96

Bobby Mitchell
Tim Skinner
Karen Cook



My commission expires: March 24, 2003

Notary Public

Permit No. 017-4258-P

