

JAN 13 1999

State of West Virginia
Division of Environmental Protection
Section of Oil and Gas22-Aug-97
API # 47- 17-04392

Permitting

Office of Oil & Gas
Well Operator's Report of Well Work

Farm name: LAW, RONALD L. Operator Well No.: RITTER 1372

LOCATION: Elevation: 1,347.00 Quadrangle: SMITHBURG

District: NEW MILTON

County: DODDRIDGE

Latitude: 6190 Feet South of 39 Deg. 17 Min. 30 Sec.

Longitude: 540 Feet West of 80 Deg. 42 Min. 30 Sec.

Company: TRIO PETROLEUM CORP.

P. O. BOX 880

GLENVILLE, WV 26351-0880

Agent: STEPHEN E. HOLLOWAY

INSPECTOR: MIKE UNDERWOOD

Permit Issued: 08/25/97

Well work commenced: 11/20/97

Well Work completed: 12/02/97

Verbal Plugging

Permission granted on:

Rotary Cable Rig

Total Depth (feet) 5,614'

Fresh water depths (ft) 128'

Salt water depths (ft) NONE

Is coal being mined in area (Y/N)? N

Coal Depths (ft): NONE


Casing & Tubing Size	Used in Drilling	Left in Well	Cement Piled Up Cu. Ft.
11-3/4"	129'	129'	C.T.S.
8-5/8"	1,562'	1,562'	C.T.S.
4-1/2"		5,518'	480 Skis.

OPEN FLOW DATA

Producing formation **DEVONIAN SHALE** Pay zone depth (ft) **SEE TREATMENT**
 Gas: Initial open flow **N/A** MCF/d Oil: Initial open flow **N/A** Bbl/d
 Final open flow **630'** MCF/d Final open flow **N/A** Bbl/d
 Time of open flow between initial and final tests **4** Hours
 Static Rock pressure **1,600** psig (surface pressure) after **48** Hours

Second producing formation _____ pay zone depth (ft) _____
 Gas: Initial open flow _____ MCF/d Oil: Initial open flow _____ Bbl/d
 Final open flow _____ MCF/d Final open flow _____ Bbl/d
 Time of open flow between initial and final tests _____ Hours
 Static rock pressure _____ psig (surface pressure) after _____ Hours

NOTE: ON BACK OF THIS FORM PUT THE FOLLOWING: 1). DETAILS OF PERFORATED INTERVALS, FRACTURING OR STIMULATION, PHYSICAL CHANGE, ETC. 2). THE WELL LOG WHICH IS A SYSTEMATIC DETAILED GEOLOGICAL RECORD OF ALL FORMATIONS, INCLUDING COAL ENCOUNTERED BY THE WELLBORE.



For: TRIO PETROLEUM CORP.

By: Daniel R. Chapman, Geologist

Date: JANUARY 5, 1998

JAN 16 1998

1st Stage: Alexander (5438-5263) 1000 gal 15% HCL, 40,000#
 20/40, 527 mcf N₂, 556 bbl foam

2nd Stage: Benson (5096-5094) 750 gal 15% HCL, 40,000# 20/40,
 534 mcf N₂, 632 bbl foam

3rd Stage: Spechly (3567-3483) 750 gal 15% HCL, 30,000#
 20/40, 324 mcf N₂, 501 bbl foam

	0	428	1/2" Stream @ 128'
Sand, Shale	0	428	1/2" Stream @ 128'
Sand, Shale, Red Rock	428	510	
Sand, Shale	510	1990	
Little Lime	1990	2003	
Blue Monday	2003	2041	
Big Lime	2041	2106	
Big Injun	2106	2196	
sand, Shale	2196	3438	
Spechly Section	3438	3697	
Shale	3697	3730	
Balltown Section	3730	4531	
Riley Section	4531	5021	
Shale	5021	5092	
Benson	5092	5098	
Shale	5098	5390	
Alexander	5390	5440	
Shale	5440	5614	T.D.

STATE OF WEST VIRGINIA
DEPARTMENT OF ENERGY, DIVISION OF OIL AND GAS
WELL WORK PERMIT APPLICATION

1) Well Operator: Trio Petroleum Corp. 50050 (0) 611

Operator's Well Number: Ritter 1372 3) Elevation: 1,347'

4) Well type: (a) Oil or Gas Issued 08/25/97

(b) If Gas: Production Underground Storage Expires 08/25/99
Deep Shallow

5) Proposed Target Formation(s): Marcellus 437

6) Proposed Total Depth: 5,900' feet

7) Approximate fresh water strata depths: N/A

8) Approximate salt water depths: 1,537'

9) Approximate coal seam depths: N/A

10) Does land contain coal seams tributary to active mine? Yes No

11) Proposed Well Work: Drill and stimulate new well.

12)

Environmental Protection
Division of
Oil & Gas
AUG 04 1997
Permitting
Office of Oil & Gas

CASING AND TUBING PROGRAM

TYPE	SPECIFICATIONS			FOOTAGE INTERVALS		CEMENT
	Size	Grade	Weight per ft.	For drilling	Left in well	
Conductor						
Fresh Water	11-3/4"	API	32#	132'	132'	38981.3 C.T.S.
Coal						
Intermediate	8-5/8"	API	23#	1,575'	1,575'	30.1 30099141.72 C.T.S.
Production	4-1/2"	API	10.5#		5,900'	500 Sk. 30099141.72
Tubing						
Liners						

PACKERS : Kind _____

Sizes _____

Depths set _____

For Division of Oil and Gas Use Only

Fee(s) paid: Well Work Permit Reclamation Fund WPCP

Plat WW-9 WW-2B Bond _____ (Type)

24110

1) Date: July 25, 1997
2) Operator's well number
Ritter 1372
3) API Well No: 47 - 017 - 4392
State County Permit

**STATE OF WEST VIRGINIA - BUREAU OF ENVIRONMENT
DIVISION OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS**

NOTICE AND APPLICATION FOR A WELL WORK PERMIT

4) Surface Owner(s) to be served: 5) (a) Coal Operator:

(a) Name Ronald L. Law Name N/A
Address P. O. Box 399 Address _____
Follansbee, WV 26037

(b) Name _____ (b) Coal Owner(s) with Declaration
Address _____ Name N/A
Address _____

(c) Name _____ Name _____
Address _____ Address _____

6) Inspector Mike Underwood (c) Coal Lessee with Declaration
Address Rt. 2, Box 135 Name N/A
Salem, WV 26426-0135 Address _____
Telephone (304) - 288-4604

TO THE PERSON(S) NAMED ABOVE TAKE NOTICE THAT:

Included is the lease or leases or other continuing contract or contracts by which I hold the right to extract oil and gas OR

Included is the information required by Chapter 22, Article 6, Section 8(d) of the Code of West Virginia (see page 2)

I certify that as required under Chapter 22 of the West Virginia Code I have served copies of this notice and application, a location plat, and accompanying documents pages 1 through 7 on the above named parties, by:

- Personal Service (Affidavit attached)
- Certified Mail (Postmarked postal receipt attached)
- Publication (Notice of Publication attached)

I have read and understand Chapter 22-6 and 38 CSR 11-18, and I agree to the terms and conditions of any permit issued under this application.

I certify under penalty of law that I have personally examined and am familiar with the information submitted on this application form and all attachments, and that based on my inquiry of those individuals immediately responsible for obtaining the information, I believe that the information is true, accurate, and complete.

I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment.

Well Operator TRIA Petroleum Corp.
By: [Signature] Stephen E. Holloway
Agent
Address P. O. Box 880
Glenville, WV 26351-0880

Telephone (304) 462-5347

Subscribed and sworn before me this 25th day of July, 1997
My commission expires 8-31-97 [Signature] Notary Public