

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Randy E Huff Descendan Operator Well No.: Lesson 510840

LOCATION: Elevation: 856' Quadrangle: Oxford 7.5'
District: Southwest County: Doddridge
Latitude: 39.148115 Feet South of _____ Deg. _____ Min. _____ Sec.
Longitude: -80.794792 Feet West of _____ Deg. _____ Min. _____ Sec.

RECEIVED
Office of Oil and Gas

AUG 29 2022

Well Type: OIL _____ GAS X

WV Department of
Environmental Protection

Company EQT Production Company Coal Operator William Lee Huff
400 Woodcliff Drive or Owner 1108 West County Road 130
Canonsburg PA 15317 Midland, TX 79706
Agent Joseph C. Mallow Coal Operator Master Mineral Holdings, LP
Permit Issued Date 3/28/2022 or Owner P.O. Box 10886
Midland, TX 79706

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of Doddridge ss:


Matthew A. Yearsley and Kevin S. Wright being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 7th day of April, 2022, and the well was plugged and filled in the following manner:

| TYPE | FROM | TO | PIPE REMOVED | LEFT |
|----------------|-------|---------|---|---------------------------------|
| Class A Cement | 6000' | 5150' | 5 1/2" 1831' | 4496' - Perfs at 3,500' / 4500' |
| Class A Cement | 3850' | 3386' | 8 5/8" None | 1681' |
| Class A Cement | 1831' | 1518' | 11 3/4" None | 671' |
| Class A Cement | 1000' | 500' | 16" None | 46' |
| Class A Cement | 200' | Surface | Tag Plugs @ 5150', 3386', 1518' | |
| | | | 10k CIBP SET IN 5 1/2" @ 6,000' / 5120' | |
| | | | | 6% Gel Between each Plug |

Description of monument: 98" of 7" Casing with Company Name, API#, and Date Plugged and that the work of plugging and filling said well was completed on the 20 day of May, 2022.

And further deponents saith not. Matthew A. Yearsley

Kevin S. Wright



Sworn and subscribe before me this 26th day of May, 2022

My commission expires: 09/15/22 [Signature]

Notary Public

Affidavit reviewed by the Office of Oil and Gas: _____ Title: _____