

west virginia department of environmental protection

Office of Oil and Gas 601 57th Street, S.E. Charleston, WV 25304 (304) 926-0450 fax: (304) 926-0452

Jim Justice, Governor Austin Caperton, Cabinet Secretary www.dep.wv.gov

PERMIT MODIFICATION APPROVAL Horizontal 6A / Horizontal 6A Well - 1

EQT PRODUCTION COMPANY 120 PROFESSIONAL PLACE BUILDING II BRIDGEPORT, WV 26330

Re: Permit Modification Approval for 516235

47-017-06747-00-00

Modifying the target formation from the Geneseo to the Marcellus.

EQT PRODUCTION COMPANY

The Office of Oil and Gas has reviewed the attached permit modification for the above referenced permit. The attached modification has been approved and well work may begin. Please be reminded that the oil and gas inspector is to be notified twenty-four (24) hours before permitted well work is commenced.

If there are any questions, please feel free to contact me at (304) 926-0450.

James A. Martin

Chief

Operator's Well Number: 516235 Farm Name: WETZEL, CATHY

U.S. WELL NUMBER: 47-017-06747-00-00

Horizontal 6A / Horizontal 6A Well - 1

Date Issued: 5/30/2017

Promoting a healthy environment.

4701706747

API NO. 47-017	_ 08747	MOD	
OPERATOR WI	ELL NO.	516235	
Well Pad Nam	e: OXF43		

STATE OF WEST VIRGINIA DEPARTMENT OF ENVIRONMENTAL PROTECTION, OFFICE OF OIL AND GAS WELL WORK PERMIT APPLICATION

1) Well Operator:	EQT Prod	uction Company	306686	Doddridge	Southwest /Cove	Oxford
		40005	Operator ID	County	District	Quadrangle
2) Operator's Well	Number: 2	16235	Well Pad	Name: OXF4	3	
3) Farm Name/Sur	face Owner:	Cathy Wetzel	Public Road	Access: RT	20	
4) Elevation, curren	nt ground:	1254' Ele	evation, proposed p	ost-construction	on: 1229'	
5) Well Type (a)	Gas X	Oil		rground Storag		
Oti						
(b)		allow X	Deep			
6) Endada a D. 1 W.		rizontal X				
6) Existing Pad: Ye						
7) Proposed Target Marcellus, 6666'	TVD, 57' thic	s), Depth(s), Antici k, 2951 PSI	pated Thickness an	d Expected Pro	essure(s):	
8) Proposed Total \	ertical Dep	th: 6666'				
9) Formation at Tot	al Vertical I	Depth: Marcellus				
10) Proposed Total	Measured D	epth: 12370'				
11) Proposed Horiz	ontal Leg Le	ength: 5066'				
12) Approximate Fr	esh Water S	trata Depths:	70, 221, 307, 382	•		
13) Method to Dete	rmine Fresh	Water Depths: By	y offset wells			
14) Approximate Sa	ltwater Dep	ths: No Saltwater	present in offset w	ells		
15) Approximate Co	oal Seam De	pths: 321'				
16) Approximate Do	epth to Possi	ble Void (coal min	e, karst, other): No	one		
17) Does Proposed virectly overlying or	well location adjacent to	contain coal seam. an active mine?	s Yes	No	×	
(a) If Yes, provide	Mine Info:	Name:				
		Depth:	W. C		···	
		Seam:				
RECEIN	/ED	Owner:				
Office of Oil	and Gas					
MAY 8	2017					
WIAT .	LO 17	$\mathcal Q$	AF			
WV Depart		n 5	f(1)		Pa	ige 1 of 3

WW-6B (04/15)

API NO. 47-017	06747	MOD	
OPERATOR WEL	L NO.	518235	
Well Pad Name	· OXF4	3	

18)

CASING AND TUBING PROGRAM

TYPE		Manu					
	Size (in)	New Or Used	<u>Grade</u>	Weight per ft. (lb/ft)	FOOTAGE: For Drilling (ft)	INTERVALS: Left in Well (ft)	CEMENT: Fill-up (Cu. Ft.)/CTS
Conductor	20	New	A-500	78.6	40	40	60 ft^3 / CTS
Fresh Water	13 3/8	New	J-55	54.5	532	532	487 ft^3 / CTS
Coal							
Intermediate	9 5/8	New	A-500	40	2426	2426	960 ft^3 / CTS
Production	5 1/2	New	P-110	20	12370	100-0	500' above top producing zone
Tubing	2 3/8		J-55	4.7		May not be run, if run set 40"	7.
Liners						above top perf or 80° inclination.	

TYPE	Size (in)	Wellbore Diameter (in)	Wall Thickness (in)	Burst Pressure (psi)	Anticipated Max. Internal Pressure (psi)	Cement Type	Cement Yield (cu. ft./k)
Conductor	20	26	.375	1378	18	Class A	
Fresh Water	13 3/8	17 1/2	.38	2700	2160	See variance 2014-17	1.19
Coal							1.19
Intermediate	9 5/8	12 3/8	.395	3950	3160	See venence 2014-17	1.19
Production	5 1/2	8 1/2	.361	12640	10112	Class A/H	1.123/2.098
Tubing	2 3/8	NA	.19	7700			1.120/2.030
Liners							

PACKERS

Kind:						
Sizes:						
Oizes.						
Depths Set:						
Depuis Set:	1	1				

REGEIVED
Office of Oil and Gas

MAY 8 2017

Off 5/d1

Page 2 of 3

WV Department of Environmental Protection WW-6B (10/14)

API	NO. 47- 017	- 08747	MON	_
	OPERATOR	WELL NO.	518235	
	Well Pad N	lame: <u>OXF4</u>	3	

19) Describe proposed well work, including	the drilling and plugging back of a	ny pilot hole:
--	-------------------------------------	----------------

Drill and complete a new horizontal well in the Marcellus Formation. Drill the vertical to an approximate depth of 4956'. Kick off and drill curve. Drill the lateral in the Marcellus. Cement casing.

20) Describe fracturing/stimulating methods in detail, including anticipated max pressure and max rate:

Hydraulic fracturing is completed in accordance with state regulations using water recycled from previously fractured wells and obtained from freshwater sources. This water is mixed with sand and a small percentage (less than 0.3%) of chemicals (including 15% Hydrochloric acid, friction reducer, biocide, and scale inhibitor), referred to in the industry as a "slickwater" completion. Maximum anticipated internal casing pressure is expected to be approximately 10000 psi, maximum anticipated treating rates are expected to average approximately 100 bpm. Stage lengths vary from 150 to 300 feet. Average approximately 250,000 gallons of water per stage. Sand sizes vary from 100 mesh to 20/40 mesh. Average approximately 250,000 pounds of sand per stage.

- 21) Total Area to be disturbed, including roads, stockpile area, pits, etc., (acres): +/-77.67
- 22) Area to be disturbed for well pad only, less access road (acres): +/- 23.31
- 23) Describe centralizer placement for each casing string:
- Surface: Bow spring centralizers One centralizer at the shoe and one spaced every 500'.
- Intermediate: Bow spring centralizers
 — One centralizer at the shoe and one spaced every 500'.
- Production: One solid body centralizer spaced every joint from production casing shoe to KOP

24) Describe all cement additives associated with each cement type:

Conductor: Class A no additives
Surface (Type 1 Cement): 0-3% Calcium Chloride. Used to speed the setting of cement slumles
Intermediate (Type 1 Cement): 0-3% Calcium Chloride. Used to speed the setting of cement slumles.

Lead (Class A Cement): 0.2% CD-20 (dispersant makes cament easier to mix). .15% SuperFL-300 (fluid loss/lengthens thickoning time) .15% SEC-10 (fluid loss) 50:50 POZ (extender)
Tail (Class H Cement): 0.2% Super CR-1 (Retarder). Lengthens thickening time. .3% Super FL-200 (fluid loss) .2% SEC-10 (Fluid loss). .2% SuperFL-350 (fluid loss) Reduces amount of water lost to formation. 50 % Calculm Carbonate. Acid solubility.


25) Proposed borehole conditioning procedures:


Surface: Circulate hole clean while rotating & reciprocating the drill string until cuttings diminish at surface. Intermediate: Circulate hole clean while rotating & reciprocating the drill string until cuttings diminish at surface.

Production: Pump marker sweep with nut plug to determine actual hole washout. Calculate a gauge holes bottoms up volume. Perform a cleanup cycle by pumping 3-5 bottoms up or until the shakers are clean. Check volume of cuttings coming across the shakers every 15 minutes.

*Note: Attach additional sheets as needed.

DAF s(ilg) Received
Office of Oil & GasPage 3 of 3





12,148' LATITUDE 3910'00" TH-

3,080' LATITUDE 3972'30" BH

W 516235

EQT Proc



west virginia department of environmental protection

Office of Oil and Gas 601 57th Street, SE Charleston, WV 25304 (304) 926-0450 (304) 926-0452 fax

Earl Ray Tomblin, Governor Randy C. Huffman, Cabinet Secretary dep.wv.gov

March 18, 2014

Nabors Completion & Production Services Company 1380 Route 286 Hwy E #121 Indiana PA 15701

Re: Cement Variance Request

Dear Sir or Madam,

This agency is approving a variance request for the cement blend listed below to be used on surface and coal protection strings for the drilling of oil and gas wells in the state of West Virginia. The variance cannot be used without requesting its use on a permit application and approval by this agency:

Type 1 (2% Calcium Chloride-Accelerator, 0.25% Super Flake-Lost Circulation, 5.2% Water, 94% Type "1" Cement)

If you have any questions regarding this matter feel free to contact me at 304-926-0499, ext. 1653.

James Peterson

Environmental Resources Specialist / Permitting

Promoting a healthy environment.



west virginia department of environmental protection

Office of Oil and Gas 601 57th Street, SE Charleston, WV 25304 (304) 926-0450 (304) 926-0452 fax

Earl Ray Tomblin, Governor Randy C. Huffman, Cabinet Secretary dep.wv.gov

BEFORE THE OFFICE OF OIL AND GAS DEPARTMENT OF ENVIRONMENTAL PROTECTION STATE OF WEST VIRGINIA

IN THE MATTER OF A VARIANCE FROM)	ORDER NO.	2014 - 17
REGULATION 35 CSR § 4-11.4/11.5/14.1)		
AND 35 CSR § 8-9.2.h. 4/5/6/8 OF THE)		
THE OPERATIONAL	Ś		
REGULATIONS OF CEMENTING OIL)		
AND GAS WELLS)		

REPORT OF THE OFFICE

Nabors Completion & Production Services Co. requests approval of a different cement blend for use in cementing surface and coal protection casing of oil and gas wells.

FINDINGS OF FACT

- 1.) Nabors Completion & Production Services Co. proposes the following cement blend:
 - 2% Calcium Chloride (Accelerator)
 - 0.25 % Super Flake (Lost Circulation)
 - 94% Type "1" Cement
 - 5.20 % Water
- Laboratory testing results indicate that the blend listed in Fact No.1 will achieve a 500
 psi compressive strength within 6 hours and a 2,435 psi compressive strength within 24
 hours.

Promoting a healthy environment

RECEIVED
Office of Oil and Gas

MAR 2 9 2017

WV Department of Environments/02/2464tjon

CONCLUSIONS OF LAW

Pursuant to Articles 6 and 6A, Chapter 22 of the Code of West Virginia, the Office of Oil and Gas has jurisdiction over the subject matter embraced in said notice, and the persons interested therein, and jurisdiction to promulgate the hereinafter prescribed Order.

Pursuant to 35 CSR § 4-11.5 and 35 CSR § 8-9.2.h.8 the Chief of the Office of Oil and Gas may approve different cement blends upon the well operator providing satisfactory proof that different cement types are adequate.

ORDER


It is ordered that Nabors Completion & Production Services Co. may use the cement blend listed in Findings of Fact No.1 for the cementing of surface and coal protection casing of oil and gas wells in the State as may be requested by oil and gas operators. The waiting time on the cement blend shall be 8 hours. The cement blend shall be mixed in strict accordance with the specifications for each blend and weight measurements made on-site to assure the cement slurries meet the minimum weight specifications. A sample shall be collected and, if after 8 hours the cement is not set up, additional time will be required. Nabors Completion & Production Services Co. shall keep a record of cement blend jobs in which the cement blend approved under this order is to be used and made available to the Office of Oil and Gas upon request.

Dated this, the 18th day of March, 2014.

IN THE NAME OF THE STATE OF WEST VIRGINIA

OFFICE OF OIL AND GAS
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OF THE STATE OF WEST VIRGINIA

James Martin, Chief Office of Oil and Gas





March 28, 2017

Mr. Gene Smith West Virginia Department of Environmental Protection Office of Oil and Gas 601 57th Street SE Charleston, WV 25304

Re: Modification of API 47-0 7-06747, 06745, 06744

Dear Mr. Smith.

Enclosed are forms WW6B, schematic, and Mylar plat, for the above API number. EQT is modifying the target formation from the Geneseo to the Marcellus. No casing was changed.

If you have any questions, please do not hesitate to contact me at (304) 848-0076.

Sincerely,

Vicki Roark

Permitting Supervisor-WV

Enc.

RECEIVED Office of Oil and Gas

MAR 2 9 2017

WV Department of Environmental Protection



May 5, 2017

West Virginia Department of Environmental Protection Office of Oil and Gas 601 57th Street SE Charleston, WV 25304

Re: Inspector sign offs 47-01706744, 06745, 06747

Dear Sir or Madam,

Enclosed are the inspector sign offs for the above API numbers.

If you have any questions, please do not hesitate to contact me at (304) 848-0076.

Sincerely,

Vicki Roark

Permitting Supervisor-WV

Enc.

REGEIVED
Office of Oil and Gas

MAY 8 2017

WV Department of Environmental Protection

4701706747

OPERATOR WELL NO. 516235
Well Pad Name: OXF43

STATE OF WEST VIRGINIA DEPARTMENT OF ENVIRONMENTAL PROTECTION, OFFICE OF OIL AND GAS WELL WORK PERMIT APPLICATION

1) Well Opera	tor: EQT F	roduction	Company	306686	Doddridge	Southwest /Cove	Oxford
				Operator ID	County	District	Quadrangle
2) Operator's V	Well Numbe	r: 516235		Well P	ad Name: OXF	43	
3) Farm Name	/Surface Ow	ner: Cath	y Wetzel	Public Re	oad Access: RT	20	
4) Elevation, c	_			levation, propose			
5) Well Type	(a) Gas Other	<u>X</u>	Oil	Un	derground Stora	ge	
	(b)If Gas	Shallow	X	Deep	_		
		Horizonta	al X				
6) Existing Pad	l: Yes or No	No					
7) Proposed Ta Marcellus, 66	rget Format 666' TVD, 57	ion(s), Dep	th(s), Antic I PSI	ipated Thickness	and Expected P	ressure(s):	
8) Proposed To	tal Vertical	Depth: 66	666'				
9) Formation at	Total Verti	cal Depth:	Marcellus				
10) Proposed T	otal Measur	ed Depth:	12370'				
11) Proposed H	orizontal Le	g Length:	5066'				
12) Approximat	te Fresh Wa	ter Strata D	epths:	70, 221, 307, 3	82'		
13) Method to I	Determine F	esh Water	Depths: B	By offset wells			
14) Approximat	te Saltwater	Depths: 1	lo Saltwate	r present in offse	t wells		
15) Approximat	te Coal Sean	n Depths:	321'				
16) Approximat	e Depth to F	ossible Vo	oid (coal mir	ne, karst, other):	None		
17) Does Propos directly overlyin	sed well locang or adjacen	ntion conta nt to an act	in coal seamive mine?	Yes	No	X	
(a) If Yes, prov	vide Mine Ir	fo: Nam	e:				
		Dept	h:				
		Seam	:				come = g grow gridg
		Own	er:			REC	Cilend Con
						Office of I	Oil and Gas

MAR 2 9 2017



WV Department of Environmered Protection 06/02/2017

4701706747

API NO. 47-_017 _ 06747

MOD

OPERATOR WELL NO. 516235
Well Pad Name: OXF43

18)

CASING AND TUBING PROGRAM

TYPE	Size (in)	New or Used	Grade	Weight per ft. (lb/ft)	FOOTAGE: For Drilling (ft)	INTERVALS: Left in Well (ft)	CEMENT: Fill-up (Cu. Ft.)/CTS
Conductor	20	New	A-500	78.6	40	40	60 ft^3 / CTS
Fresh Water	13 3/8	New	J-55	54.5	532	532	487 ft^3 / CTS
Coal							107 11 07 013
Intermediate	9 5/8	New	A-500	40	2426	2426	960 ft^3 / CTS
Production	5 1/2	New	P-110	20	12370	40070	500' above top producing zone
Tubing	2 3/8		J-55	4.7		May not be run, if run set 40'	
Liners						above top perf or 80° inclination.	

ТҮРЕ	Size (in)	Wellbore Diameter (in)	<u>Wall</u> <u>Thickness</u> <u>(in)</u>	Burst Pressure (psi)	Anticipated Max. Internal Pressure (psi)	Cement Type	Cement Yield
Conductor	20	26	.375	1378	18	Class A	(cu. ft./k) 1.18
Fresh Water	13 3/8	17 1/2	.38	2700	2160	See variance 2014-17	1.19
Coal							1.10
Intermediate	9 5/8	12 3/8	.395	3950	3160	See variance 2014-17	1.19
Production	5 1/2	8 1/2	.361	12640	10112	Class A/H	1.123/2.098
Tubing	2 3/8	NA	.19	7700			1.120/2.000
Liners							

PACKERS

Kind:		
Sizes:		
Depths Set:		



OPERATOR WELL	NO.	516235	
Well Pad Name:	OXF43	3	

19) Describe proposed well work, including the drilling and plugging back of any pilot hole:
--

Drill and complete a new horizontal well in the Marcellus Formation. Drill the vertical to an approximate depth of 4956'. Kick off and drill curve. Drill the lateral in the Marcellus. Cement casing.

20) Describe fracturing/stimulating methods in detail, including anticipated max pressure and max rate:

Hydraulic fracturing is completed in accordance with state regulations using water recycled from previously fractured wells and obtained from freshwater sources. This water is mixed with sand and a small percentage (less than 0.3%) of chemicals (including 15% Hydrochloric acid, friction reducer, biocide, and scale inhibitor), referred to in the industry as a "slickwater" completion. Maximum anticipated internal casing pressure is expected to be approximately 10000 psi, maximum anticipated treating rates are expected to average approximately 100 bpm. Stage lengths vary from 150 to 300 feet. Average approximately 250,000 gallons of water per stage. Sand sizes vary from 100 mesh to 20/40 mesh. Average approximately 250,000 pounds of sand per stage.

- 21) Total Area to be disturbed, including roads, stockpile area, pits, etc., (acres): +/-77.67
- 22) Area to be disturbed for well pad only, less access road (acres): +/- 23.31
- 23) Describe centralizer placement for each casing string:
- Surface: Bow spring centralizers One centralizer at the shoe and one spaced every 500'.
- Intermediate: Bow spring centralizers— One centralizer at the shoe and one spaced every 500'.
- Production: One solid body centralizer spaced every joint from production casing shoe to KOP

24) Describe all cement additives associated with each cement type:

Surface (Type 1 Cement): 0-3% Calcium Chloride. Used to speed the setting of cement slurries Intermediate (Type 1 Cement): 0-3% Calcium Chloride. Used to speed the setting of cement slurries.

Lead (Class A Cement): 0.2% CD-20 (dispersant makes cement easier to mix). .15% SuperFL-300 (fluid loss/lengthens thickening time) .15% SEC-10 (fluid loss) 50:50 POZ (extender) Tail (Class H Cement): 0.2% Super CR-1 (Retarder). Lengthens thickening time. .3% Super FL-200 (fluid loss) .2% SEC-10 (Fluid loss). .2% SuperFL-350 (fluid loss) Reduces amount of water lost to formation. 60 % Calcuim Carbonate. Acid solubility.

25) Proposed borehole conditioning procedures:

Surface: Circulate hole clean while rotating & reciprocating the drill string until cuttings diminish at surface. Intermediate: Circulate hole clean while rotating & reciprocating the drill string until cuttings diminish at surface.

Production: Pump marker sweep with nut plug to determine actual hole washout. Calculate a gauge holes bottoms up volume. Perform a cleanup cycle by pumping 3-5 bottoms up or until the shakers are dean. Check volume of cuttings coming across the shakers every 15 minutes. Office of Oil and Gas

*Note: Attach additional sheets as needed.

MAR 2 9 2017





