

Latitude 39° 17' 30"

80° 52' 30"

Longitude

75'
+

Topo Location

7.5' Loc. 1.905 15' Loc. 4.785
0.90W (calc.) 3.13W

Company C-531

Farm R. Ellafertt

15' Quad Wst Union SC
(sec.)

7.5' Quad Pennsboro

District Central

WELL LOCATION PLAT

County 017 Permit 30116

Dodd. 116A


Central District, Doddridge County, W. Va.
 By Hope Cons. & Ref. Co.; 445 W. Main St., Clarksburg, W. Va.
 On 133 acres, surface and mineral rights owned by Ellifritt Heirs,
 Olive Ellifritt, Greenwood, W. Va.
 Elevation, 944' L.
 10" casing, 433'; 8 1/4", 1496'; 6-5/8", 1809'.
 Coal was encountered at 150-153 and 624-630'.
 Abandonment reported to Dept. of Mines July 18, 1935.
 No oil, gas or water encountered below Maxton Sand.
 Well was shot at 1807-1813'.
 Oil well.

	Top.	Bottom.	Thickness.
Native coal	150	- 153	3
Pittsburgh Coal	624	- 630	6
Little Dunkard Sand	982	- 1063	81
Big Dunkard Sand	1123	- 1165	42
First Salt Sand (water, 1474')	1405	- 1498	93
Maxton Sand (oil, 1808-1813')	1791	- 1820	29
Big Injun Sand	1918	- 1985	67
Squaw Sand	1987	- 2008	21
Total depth		2030	

CLARKSBURG, W. VA.,
 WELL NO 811
 OWNER OLIVE ELIFFRITT
 ADDRESS
 CARROLL COUNTY, W. VA.
 COMPLETION DATA SHEET
 NO 2
 FORMATION RECORD
 DATE OF COMPLETION July 1935
 COUNTY W. VA.

Name	Color	Character	(In line or water)	Top	Bottom	Thickness	Total Depth	Remarks
Native Coal				180	185	5'		
Pittsburgh Coal				684	690	6'		
LITTLE DISTRICT SAND				968	1045	81'		
Big District Sand				1125	1166	41'		
First Sand				1408	1488	80'		
Second Sand				1791	1880	89'		
Big Injan				1918	1986	67'		
Sandy Sand				1987	2008	21'	2030	
No oil gas or water encountered below Marsh Sand.								

shot
 Well was not shot at 1607-1615 feet; well was shot at 1607-1615 feet.
 Salt
 Fresh water at 1674 feet; fresh water at 1674 feet.
 producing
 Well was not producing.
 July 1935, 1935.
 Date
 Approved Hays Construction & Drilling Co.
 Owner
 By



of the
 Carlsburg, W. Va., on the
 forming a part of
 County, W. Va.

WEST VIRGINIA DEPARTMENT OF MINES

(FUEL AND GAS DIVISION)

PRELIMINARY DATA SHEET NO. 1

No. D-1114 Well No. 881
Hope Construction & Refining Co. Company of 646 West Main St.
Charleston, W. Va., on the OLIVE ELIZABETH Mine
containing 123 acres. Location Bohannon District, in Bohannon County, West Virginia

The surface of the above tract is owned in fee by ELIZABETH MAIRE & OLIVE ELIZABETH
of Green Bay, W. Va. address, and the mineral rights are owned by
ELIZABETH MAIRE of Greenwood, W. Va.

The oil and gas privileges are held under lease by the above named company, and this well is drilled under permit
No. 123 issued by the West Virginia Department of Mines, Oil and Gas Division

Elevation of surface at top of well 944 feet
The number of feet of the different sized casings used in the well:

<u>633</u> feet	<u>10"</u> size, cas.	<u>1496</u> feet	<u>6 1/2"</u> size, cas.	_____ feet
<u>1800</u> feet	<u>6-5/8"</u> size, cas.	_____ feet	_____ size, cas.	_____ feet
_____ feet	_____ size, cas.	_____ feet	_____ size, cas.	_____ feet
_____ feet	_____ size, cas.	_____ feet	_____ size, cas.	_____ feet

_____ packer of _____ size, set at _____ feet to _____ feet
_____ packer of _____ size, set at _____ feet to _____ feet
Coal was encountered at 150 feet, thick ness 36 inches, and of 684 feet; thickness _____ inches; and at _____ feet; thickness _____ inches.

Liners were used as follows: (Give details) _____

July 18th, 1935. Date.

AFFIDAVIT IN TRIPLICATE TO TIME AND MANNER OF PLUGGING AND FILLING WELL

(REQUIREMENTS OF SECTION 3, ARTICLE 4, CHAPTER 23 OF THE CODE.)
WEST VIRGINIA DEPARTMENT OF MINES
(FUEL AND GAS DIVISION)

No coal operations in this vicinity. Hope Construction & Refining Co.
Name of well operator
Charleston, W. Va.
August 5th, 1935. is
WELL AND LOCATION
County
District
County

Well No. 881
OLIVE ELIZABETH Mine
Form

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of Bohannon

I, Charles J. Bohannon, being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by Hope Mineral Gas Company, well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 18th day of July, 1935, and that the well was plugged and filled in the following manner:

Manner in which well was plugged:
Installed permanent bridge at 1800 ft. and filled hole with clay to 1800 ft removed 6 5/8" casing, 6 1/2" mudrill lead plug 1796 6 1/2" mudrill lead plug 1796
Drove 6 1/2" mudrill lead plug at 1496' and plug did not stop until depth of 1895' filled with shrink stone to 1448 drove 100 lbs lead wool in 6 1/2" casing and casing shot off at 1895'
Manner in which coal was plugged:
Bridged hole at 641' and cemented from 641' to 649' using 18 sacks cement
Drove 10" wood plug at 595' filled with clay to 439' pulled 10" casing filled with clay to surface of ground.

Description of monument:
Rig still standing, will set monument when rig is torn down.

and that the work of plugging and filling said well was completed on the 18th day of August, 1935.
And further deponents wish not
Charles J. Bohannon