


39 12 30

LATITUDE

80° 45'

LONGITUDE



7'5 OGIS topo location

7.5' loc 2.22 S 15' loc _____
 ' 0.26 W (calc.) _____

Company _____

Farm _____

Quad Oxford _____

County _____

District Southwest _____

WELL LOCATION MAP

File No. 017-30254

STATE OF WEST VIRGINIA
DEPARTMENT OF MINES
OIL AND GAS DIVISION

201

WELL RECORD

Permit No. 000-254-A


Oil or ~~Gas~~ Well Oil
(Kind)

Company Hope Construction & Refining Co.
 Address 445 West Main St. Clarksburg, W. Va.
 Farm S. W. Stout Acres 1427
 Location (waters) SF of Hughes River
 Well No. 1320 Elev. 951'
 District Southwest County Doddridge
 The surface of tract is owned in fee by _____
 Address _____
 Mineral rights are owned by _____
 Address _____
 Drilling commenced Sept. 5, 1899
 Drilling completed Oct. 31, 1899
 Date shot May, 1928 Depth of shot 2500
 Open Flow /10ths Water in _____ Inch
 /10ths Merc. in _____ Inch
 Volume _____ Cu. Ft.
 Rock Pressure _____ lbs. _____ hrs.
 Oil _____ bbls., 1st 24 hrs.
 Fresh water none reported feet _____ feet
 Salt water none reported feet _____ feet

Casing and Tubing	Used in Drilling	Left in Well	Packers
Size			Kind of Packer
16			
13			
10	385	Pulled	Size of
8 1/4	1025	pulled	
6 5/8	1950	1950	Depth set
5 3/16	2494	2494	
3			Perf. top
2	2519	2519	Perf. bottom
Liners Used			Perf. top
			Perf. bottom

Not cemented
 CASING CEMENTED _____ SIZE _____ No. FT. _____ Date _____
none recorded
 COAL WAS ENCOUNTERED AT _____ FEET _____ INCHES
 _____ FEET _____ INCHES FEET _____ INCHES
 _____ FEET _____ INCHES FEET _____ INCHES

Formation	Color	Hard or Soft	Top	Bottom	Oil Gas or Water	Depth Found	Remarks
Red Rock			800	1000			
Cow Run Sand			1025	1040			
First Salt Sand			1200	1400			
Maxon Sand			1625	1650			
Big Lime			1730	1830			
Big Injun Sand			1830	1930	show oil	1830	
Gordon Stray			2475	2495			
Gordon Sand			2499	2504	oil	2499	
Total Depth				2519			



ellu

Southwest District, Doddridge County, W. Va.
 By Hope Construction & Refining Co., 445 W. Main St., Clarksburg, W. Va.
 On 1427 acres, on South Fork of Hughes River.
 Elevation, 951' L.
 Drilling commenced Sept. 5, 1899; completed, Oct. 31, 1899.
 Shot, May, 1928, at 2500'.
 No water reported.
 10" casing, 385' (pulled); 8 $\frac{1}{4}$ " , 1025' (pulled); 6 $\frac{5}{8}$ " , 1950';
 5 $\frac{7}{8}$ " , 2494'; 2" tubing, 2519'.
 Casing not cemented. No coal was encountered.
 Oil well. Abandonment reported to Dept. of Mines Oct. 27, 1938.
 Record to RCT from Mrs. Griffith Nov. 16, 1938.

	Top.	Bottom.
Red rock	800	- 1000
Cow Run Sand	1025	-- 1040
First Salt Sand	1200	- 1400
Maxton Sand	1625	- 1650
Big Lime	1730	- 1830
Big Injun Sand (show oil, 1830')	1830	- 1930
Gordon Stray Sand	2475	- 2495
Gordon Sand (oil, 2499')	2499	- 2504
Total depth		2519