


LATITUDE

80'45

OGIS 7.5' loc



LONGITUDE

7.5 OGIS topo location

7.5' loc	<u>0.85 S</u>	15' loc	_____
	<u>0.26 W</u>	(calc.)	_____

Company _____

Farm _____

Quad Oxford _____

County _____

District Southwest _____

WELL LOCATION MAP

File No. 017-30255

STATE OF WEST VIRGINIA
DEPARTMENT OF MINES
OIL AND GAS DIVISION

203

WELL RECORD

Permit No. 800-255-A

Oil or Gas Well 011
(Kind)


Company Hope Construcion & Refining Co.
 Address 445 West Main St. Clarksburg, W. Va.
 Farm W.M. Stout Acres 340
 Location (waters) SF Hughes River
 Well No. 1344 Elev. 1273
 District Southwest County Doddridge
 The surface of tract is owned in fee by _____
 Address _____
 Mineral rights are owned by _____
 Address _____
 Drilling commenced Feb. 6, 1901
 Drilling completed Mar. 31, 1901
 Date shot May, 1927 Depth of shot 2712
 Open Flow /10ths Water in _____ Inch
 /10ths Merc. in _____ Inch
 Volume _____ Cu. Ft.
 Rock Pressure _____ lbs. _____ hrs.
 Oil None recorded _____ bbls., 1st 24 hrs.
 Fresh water None recorded _____ feet
 Salt water 1490 _____ feet

Casing and Tubing	Used in Drilling	Left in Well	Packers
Size			
16.			Kind of Packer
13.			
10.	625	Pulled	Size of
8 1/4	1235	Pulled	
6 5/8	1575	1575	Depth set
	2180	2180	
5 3/16			
3.			Perf. top
2.	2725	2725	Perf. bottom
Liners Used			Perf. top
			Perf. bottom

Not cemented

CASING CEMENTED _____ SIZE _____ No. FT. _____ Date _____
None recorded
 COAL WAS ENCOUNTERED AT _____ FEET _____ INCHES
 _____ FEET _____ INCHES FEET _____ INCHES
 _____ FEET _____ INCHES FEET _____ INCHES

Formation	Color	Hard or Soft	Top	Bottom	Oil Gas or Water	Depth Found	Remarks
Red Rock cave			950	1200			
First Cow Run Sand			1235	1255			
First Salt Sand			1490	1590	Water	1490	
Maxon Sand			1800	1825			
Big Lime			1980	2040			
Big Injun Sand			2040	2140	Gas	2130	
Gordon Stray			2690	2705			
Gordon Sand			2710	2715	Oil	2710	
Total depth				2735			



Southwest District, Doddridge County, W. Va.
 By Hope Construction & Refining Co., 445 W. Main St., Clarksburg, W. Va.
 On 340 acres, on South Fork of Hughes River.
 Elevation, 1273' L.
 Drilling commenced Feb. 6, 1901; completed, March 31, 1901.
 Shot, May, 1927, at 2712'.
 No fresh water recorded; salt water at 1490'.
 10" casing, 625' (pulled); 8¹/₄" , 1235' (pulled); 6¹/₄" , 1575';
 5³/₁₆" , 2180'; 2" tubing, 2725'.
 Casing not cemented. No coal was encountered.
 Oil well. Abandonment reported to Dept. of Mines Oct. 21, 1938.
 Record to RCT from Mrs. Griffith Nov. 16, 1938.

	Top.	Bottom.
Red rock cave	950	- 1200
First Cow Run Sand	1235	- 1255
First Salt Sand (water, 1490')	1490	- 1590
Maxton Sand	1800	- 1825
Big Lime	1980	- 2040
Big Injun Sand (gas, 2130')	2040	- 2140
Gordon Stray Sand	2690	- 2705
Gordon Sand (oil, 2710')	2710	- 2715
Total depth		2735