



STATE OF WEST VIRGINIA  
DEPARTMENT OF MINES  
OIL AND GAS DIVISION

733

WELL RECORD

Aband  
Permit No. pod-286-A  
West Union F.C.


Oil or Gas Well Oil  
(Kind)

Company Clifton Oil & Gas Company  
Address Box # 1042 Parkersburg, W.Va.  
Farm Lewis Maxwell Heirs Acres 105  
Location (waters) Middle Island Creek  
Well No. 1 Elev. 1053  
District West Union County Doddridge  
The surface of tract is owned in fee by \_\_\_\_\_  
Address \_\_\_\_\_  
Mineral rights are owned by \_\_\_\_\_  
Address \_\_\_\_\_  
Drilling commenced May 1st 1914  
Drilling completed May 30th 1914  
Date shot Aug. 7, 1915 Depth of shot 1996  
Open Flow /10ths Water in \_\_\_\_\_ Inch  
14 /10ths Merc. in 6 5/8 Inch  
Volume 5323 m.c.f. Cu. Ft.  
Rock Pressure \_\_\_\_\_ lbs. \_\_\_\_\_ hrs.  
Oil Show of Oil at 964' bbls., 1st 24 hrs.  
Fresh water 80' feet \_\_\_\_\_ feet  
Salt water \_\_\_\_\_ feet \_\_\_\_\_ feet

Casing and Tubing	Used in Drilling	Left in Well	Packers
Size			
16			Kind of Packer
13			
10	289	289	Size of
8 1/4	1126	1126	
6 5/8	1936	1936	Depth set
5 3/16			
3			Perf. top
2	2010	2010	Perf. bottom
Liners Used			Perf. top
			Perf. bottom

CASING CEMENTED \_\_\_\_\_ SIZE \_\_\_\_\_ No. FT. \_\_\_\_\_ Dat \_\_\_\_\_  
COAL WAS ENCOUNTERED AT 407 FEET \_\_\_\_\_ INCHES  
656 FEET \_\_\_\_\_ INCHES \_\_\_\_\_ FEET \_\_\_\_\_ INCHES  
\_\_\_\_\_ FEET \_\_\_\_\_ INCHES \_\_\_\_\_ FEET \_\_\_\_\_ INCHES

Formation	Color	Hard or Soft	Top	Bottom	Oil Gas or Water	Depth Found	Remarks
Conductor				12			
Native Coal			407	410	Water at 80'		
Pittsburgh Coal			656	658			
Little Dunkard Sand			944	984	show of Oil at 964		
Big Dunkard Sand			1124	1190			
Gas Sand			1235	1245			
First Salt Sand			1300	1411			
Second Salt Sand			1485	1550			
3rd Salt Sand			1570	1705			
Maxon Sand			1825	1860			
Red Rock			1865	1875			
Little Lime			1875	1895			
Pencil Cave			1895	1905			
Big Lime			1925	1995			
Big Injun Sand			1995				
Gas			1996				
Total first - <del>Summit</del> Drilling				2010			
" second drilling				2142			



Formation	Color	Hard or Soft	Top	Bottom	Oil, Gas or Water	Depth Found	Remarks

Date July 19, 1939, 19

**CLIFTON OIL & GAS COMPANY**

APPROVED [Signature], Owner

**General Manager.**

By \_\_\_\_\_

(Title)

