



STATE OF WEST VIRGINIA
DEPARTMENT OF MINES
OIL AND GAS DIVISION

716

Permit No. 927-A

WELL RECORD

Oil or Gas Well (KIND)


Company Hope Natural Gas Company.
 Address 445 West Main St. Clarksburg, W. Va.
 Farm Jennie M. Bee Acres 166
 Location (waters) _____
 Well No. 6069 Elev. 1291
 District McClellan County Dodderidge
 The surface of tract is owned in fee by _____
 Address _____
 Mineral rights are owned by _____
 Address _____
 Drilling commenced June 10, 1911
 Drilling completed August 12, 1911
 Date Shot _____ From _____ To _____
 With _____
 Open Flow /10ths Water in _____ Inch
 /10ths Merc. in _____ Inch
 Volume _____ Cu. Ft.
 Rock Pressure _____ lbs. _____ hrs.
 Oil _____ bbls., 1st 24 hrs.
 Fresh water none recorded feet _____ feet
 Salt water none recorded feet _____ feet

Casing and Tubing	Used in Drilling	Left in Well	Packers
Size			Kind of Packer
16			
13			
10	245	245	Size of
8 1/4	1410	Pulled	
6 5/8	2214	2214	Depth set
5 3/16			
3	3083	3083	Perf. top
2			Perf. bottom
Liners Used			Perf. top
			Perf. bottom

CASING CEMENTED _____ SIZE NOT No. Ft. _____ Date _____

COAL WAS ENCOUNTERED AT 870 FEET 60 INCHES
 _____ FEET _____ INCHES FEET _____ INCHES
 _____ FEET _____ INCHES FEET _____ INCHES

Formation	Color	Hard or Soft	Top	Bottom	Oil, Gas or Water	Depth Found	Remarks
Coal			870	882			
Dunkard			1370	1435			
Big Injun			2216	2330			
Gordon			2968	2990	Gas	2969	
Fourth			2998	3015	Gas	3000	
Total depth				3057			



(Over) **SEP - 9 1950**

Formation	Color	Hard or Soft	Top	Bottom	Oil, Gas or Water	Depth Found	Remarks

Date May 18, 1950, 19

APPROVED Hope Natural Gas Company., Owner

By _____ (Title)

(Title)

JENNIE M. BEE NO. 6069 WELL.

827A

McClellan District, Doddridge County, W. Va.
 By Hope Natural Gas Co., 445 W. Main St., Clarksburg, W. Va.
 Abandoned under permit Ded-.....-A7
 On 166 acres.

Elevation, 1291' L.

Drilling commenced June 10, 1911; completed Aug. 12, 1911.

No water recorded.

10" casing, 245'; 8 1/4", 1410' (pulled); 6 5/8", 2214'; 3" tubing, 3083'.

Casing not cemented.

Coal was encountered at 870-882'. (1) (60" thick).

Gas well. Record to Dept. of Mines dated May 18, 1950.

Record to RCF from Mrs. Griffith Sept. 9, 1950. Old File No. 716.

	Top.	Bottom.
Coal	870	- 882
Dunkard Sand	1370	- 1435
Big Injun Sand	2216	- 2330
Gordon Sand (gas, 2969')	2968	- 2990
Fourth Sand (gas, 3000')	2998	- 3015
Total depth		3057