

Surface owned by Jane A. Baker.
 Address: Mrs. Jane A. Baker, Ashley, Doddridge County, W. Va.
 No coal ever sold under this tract of land, if any,
 it belongs to the owner of the surface.

New Location
 Drill Deeper
 Abandonment

On 800' Map N37, Sqs. 53-4 W3-4.

Company Randall-Zogg Supply Co.
 Address Owensboro, Ky.
 Farm Ash Heirs
 Tract _____ Acres 91 Lease No. _____
 Well (Farm) No. 1 Serial No. _____
 Elevation (Spirit Level) Floor - 759.29
Ground - 757.09
 Quadrangle Centerpoint
 County Doddridge District McClellan
 Engineer A.L. Headley
 Engineer's Registration No. 2028
 File No. _____ Drawing No. _____
 Date July 20th, 1949 Scale 1" = 400 Feet

STATE OF WEST VIRGINIA
 DEPARTMENT OF MINES
 OIL AND GAS DIVISION
 CHARLESTON

WELL LOCATION MAP
 FILE NO. DOD-855-A

+ Denotes location of well on United States Topographic Maps, scale 1 to 62,500, latitude and longitude lines being represented by border lines as shown.

- Denotes one inch spaces on border line of original tracing.



STATE OF WEST VIRGINIA
DEPARTMENT OF MINES
OIL AND GAS DIVISION

869

AP 855-A

WELL RECORD

Permit No. _____

Oil or Gas Well **OIL**
(KIND)


Company W. D. GRIBBLE
~~W. D. GRIBBLE SUPPLY COMPANY~~
WEST UNION, W. VA.
Address 301 5th, CHARLESTON, W. VA.
Farm Ash Hires Acres 91
Location (waters) McClroy Creek
Well No. One (1) Elev. 757.00
District McClellan County Boydridge
The surface of tract is owned in fee by Mrs. Jane A. Baker,
Address Ashley, W. Va.
Mineral rights are owned by Mrs. Jane A. Baker,
Address Ashley, W. Va.
Drilling commenced _____
Drilling completed _____
Date Shot SEE BELOW From _____ To _____
With _____
Open Flow /10ths Water in _____ Inch
/10ths Merc. in _____ Inch
Volume _____ Cu. Ft.
Rock Pressure _____ lbs. _____ hrs.
Oil _____ bbls., 1st 24 hrs.
Fresh water _____ feet _____ feet
Salt water _____ feet _____ feet

Casing and Tubing	Used in Drilling	Left in Well	Packers
Size			
16			Kind of Packer
13	31'	31'	
10	224'	169'	Size of
8 1/4	1028'		
6 5/8	1757'	1757'	Depth set
5 3/16			
3			Perf. top
2	1953'	1953'	Perf. bottom
Liners Used			Perf. top
			Perf. bottom

CASING CEMENTED _____ SIZE _____ No. Ft. _____ Da _____

COAL WAS ENCOUNTERED AT 475 FEET 24 INCHES
____ FEET _____ INCHES _____ FEET _____ INCHES
____ FEET _____ INCHES _____ FEET _____ INCHES

Formation	Color	Hard or Soft	Top	Bottom	Oil, Gas or Water	Depth Found	Remarks
Pittsburgh Coal			475'	475'			
Maxon Sand			1590'	1625'			
Big Lime			1747'	1827'			
Big Injun Sand			1827'	1931'	Oil & Gas	1919'	
Total Depth				1953'			
SHOT RECORD							
	<u>DATE OF SHOT</u>		<u>NO. OF QTS.</u>		<u>TOP OF SHOT</u>		
	11-12-24		50		1919'		
	5-8-29		50		1917'		
NOTE: The 10" casing could not be located at well.							



DEC 20 1952

ASH HEIRS NO. 1 WELL.

855A

McClellan District, Doddridge County, W. Va.

By W. D. Griddle, West Union, W. Va.

Abandoned under permit No.-A7

On 91 acres, on McElroy Creek.

Elevation, 757.09' L.

Surface and minerals owned by Mrs. Jane A. Baker, Ashley, W. Va.

Date of completion not given.

Shot 11-12-24, with 30 qts., at 1919' (top of shot); 5-8-29, with 50 qts., top of shot, 1917'.

13" casing, 31'; 10", 224' (168' left in); 8½" casing, 1028' (pulled); 6¾", 1767'; 2" tubing, 1953'. NOTE: The 10" casing could not be located at well.

Coal was encountered at 473-475'.

Oil well. Record to Dept. of Mines dated Nov. 16, 1950.

Record to RCT from Mrs. Griffith Dec. 2, 1952. O.F.No.869.

	Top.	Bottom.
Pittsburgh Coal	473	475
Maxton Sand	1590	1625
Big Lime	1747	1827
Big Injun Sand (oil and gas, 1919')	1827	1931
Total depth		1953