

950A

McClellan District, Doddridge County, W. Va.

By J. P. Droppleman, West Union, W. Va.

Abandoned under permit No. 1280-47

On.....acres.

Elevation, ..... l.

Surface owned by Homer Weckley, Morgansville, W. Va., and minerals by J. B. Posey, West Union, W. Va.

Drilling completed Dec. 10, 1916.

10" casing, 509' (gulled); 8 1/2", 1233' (gulled); 6", 2101'; 5", 1253'; 2" tubing, 2272'.

Oil well. Record to Dept. of Mines stamped Oct. 15, 1952.

Record to RPT from Mrs. Griffith Dec. 10, 1952. O.P. No. 882.

See plat 31071?  
70507? 30224

	Top.	Bottom.
Native coal	246	- 249
Pittsburgh coal	726	- 778
Red rock	940	- 1102
Cow Run Sand	1102	- 1127
1st Salt Sand	1421	- 1464
2nd Salt Sand	1528	- 1627
3rd Salt Sand	1782	- 1831
Maxton Sand	1876	- 1888
Little Lime	2051	- 2075
Pencil Gave	2075	- 2078
Big lime	2078	- 2167
Big Injun Sand (oil, 2224')	2167	- 2278
Total depth		2284

See plat 224A

Wes 017 70 507

CAN NOT locate  
NEED Plat



STATE OF WEST VIRGINIA  
DEPARTMENT OF MINES  
OIL AND GAS DIVISION

881

WELL RECORD

Permit No. 900-950-A Oil or Gas Well \_\_\_\_\_ (KIND)


Company J. P. Droppelman et al  
 Address West Union, W. Va.  
 Farm W. H. Foley Acres \_\_\_\_\_  
 Location (waters) \_\_\_\_\_  
 Well No. 1280 Elev. \_\_\_\_\_  
 District McClellan County Doddridge  
 The surface of tract is owned in fee by Homer Weekley  
Morganville, W. Va. Address \_\_\_\_\_  
 Mineral rights are owned by J. B. Foley  
West Union, W. Va. Address \_\_\_\_\_  
 Drilling commenced \_\_\_\_\_  
 Drilling completed December 10, 1916  
 Date Shot From \_\_\_\_\_ To \_\_\_\_\_  
 With \_\_\_\_\_  
 Open Flow /10ths Water in \_\_\_\_\_ Inch  
 /10ths Merc. in \_\_\_\_\_ Inch  
 Volume \_\_\_\_\_ Cu. Ft.  
 Rock Pressure \_\_\_\_\_ lbs. \_\_\_\_\_ hrs.  
 Oil \_\_\_\_\_ bbls., 1st 24 hrs.  
 Fresh water \_\_\_\_\_ feet \_\_\_\_\_ feet  
 Salt water \_\_\_\_\_ feet \_\_\_\_\_ feet

Casing and Tubing	Used in Drilling	Left in Well	Packers
Size			
16			Kind of Packer _____
13			
10	507'		Size of _____
8 3/4	1233'	?	
6 3/8	2101'	2101'	Depth set _____
5 3/16	1253	1253'	
3			Perf. top _____
2	2272'	2272'	Perf. bottom _____
Liners Used			Perf. top _____
			Perf. bottom _____

CASING CEMENTED \_\_\_\_\_ SIZE \_\_\_\_\_ No. Ft. \_\_\_\_\_ Date \_\_\_\_\_

COAL WAS ENCOUNTERED AT \_\_\_\_\_ FEET \_\_\_\_\_ INCHES  
 \_\_\_\_\_ FEET \_\_\_\_\_ INCHES FEET \_\_\_\_\_ INCHES  
 \_\_\_\_\_ FEET \_\_\_\_\_ INCHES FEET \_\_\_\_\_ INCHES

Formation	Color	Hard or Soft	Top	Bottom	Oil, Gas or Water	Depth Found	Remarks
Native Coal			246	249			
Pittsburgh Coal			726	728			
Red Rock			940	1102			
Cow Run			1102	1127			
1st Salt Sand			1421	1464			
2nd Salt Sand			1528	1627			
3rd Salt Sand			1782	1831			
Maxon Sand			1876	1888			
Little Lime			2051	2075			
Pencil Vase			2075	2078			
Big Lime			2078	2167			
Big Injun			2167	2278			
Total Depth				2284	Oil 2224'		



Dodd-950A

**AFFIDAVIT OF PLUGGING AND FILLING WELL**

AFFIDAVIT SHOULD BE MADE IN TRIPPLICATE. ONE COPY MAILED TO THE DEPARTMENT ONE COPY TO BE RETAINED BY THE WELL OPERATOR AND THE THIRD COPY AND SEVERAL COPIES IF REQUIRED SHOULD BE MAILED TO EACH COAL OPERATOR AT THEIR RESPECTIVE ADDRESSES

COAL OPERATOR OR OWNER J. P. Droppleman et al  
NAME OF WELL OPERATOR  
West Union, W. Va.  
COMPLETE ADDRESS

ADDRESS \_\_\_\_\_

COAL OPERATOR OR OWNER \_\_\_\_\_ 10  
WELL AND LOCATION  
McGlellan District

ADDRESS \_\_\_\_\_

LEASE OR PROPERTY OWNER Doddridge County  
WELL No. 1250  
V. B. Foley Farm  
ADDRESS

STATE INSPECTOR SUPERVISING PLUGGING Harry V. Mase

**AFFIDAVIT**

*017-950A*

STATE OF WEST VIRGINIA,

County of Kanawha } ss:

Thomas Odell and Olney Reed  
 being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by J. P. Droppleman well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 21 day of October, 1952, and that the well was plugged and filled in the following manner:

CASE OR HOME RECORD	FILLING MATERIAL	PLUGS USED	CASING	
			COG PULLED	COG LEFT IN
FORMATION		SIZE & KIND		
	<u>Fern. bridge</u>	<u>Free top 2150</u>	<u>2" tubing</u>	<u>2236</u>
	<u>Cem. &amp; stone 2150 - 2135</u>			
<u>Filled in pipe</u>	<u>Clay 2135 - 1890</u>			
	<u>Cem. &amp; stone 1890 - 1870</u>	<u>5 1/2" sec.</u>	<u>1256</u>	<u>0</u>
<u>Fern. bridge in pipe tree top</u>	<u>Cem. &amp; stone 1225 - 1210</u>			
	<u>Clay 1210 - 1095</u>			
	<u>Cem. &amp; stone 1095 - 1080</u>			
	<u>Fern. bridge tree top 758</u>	<u>7" O. D.</u>	<u>927</u>	<u>117 1/2</u>
	<u>Clay &amp; stone 765 - 758</u>			
	<u>Cement 758 - 700</u>			
	<u>Clay 700 - 250</u>			
	<u>Cement 250 - 240</u>			
	<u>Stone 240 - 230</u>			
	<u>Clay 230 - 000</u>			
COAL SEAMS		DESCRIPTION OF MONUMENT		
		<u>J. P. Droppleman et al</u>		
		<u>V. B. Foley #1250</u>		
		<u>10-21 thru 28-52</u>		

and that the work of plugging and filling said well was completed on the 21 day of October, 1952

And further deponents saith not.

*Thomas Odell*  
*Olney Reed*

Sworn to and subscribed before me this 4 day of December, 1952