



STATE OF WEST VIRGINIA
DEPARTMENT OF MINES
OIL AND GAS DIVISION

1027

WELL RECORD

Permit No. 1050-A


Oil or Gas Well GAS
(KIND)

Company Carnegie Natural Gas Company
Address 1015 Frick Building, Pittsburgh 19, Pa.
Farm D. A. Dotson Acres 100
Location (waters) Elk Lick Run
Well No. 532 Elev. 771
District McClellan County Doddridge
The surface of tract is owned in fee by Homer C. Ash
Star Route Address West Union, W. Va.
Mineral rights are owned by See below
Address _____
Drilling commenced 9-20-15
Drilling completed 10-30-15
Date Shot _____ From _____ To _____
With _____
Open Flow 1 1/4 10ths Water in 6-5/8 Inch
_____ /10ths Merc. in _____ Inch
Volume _____ Cu. Ft.
Rock Pressure 375 lbs. _____ hrs.
Oil _____ bbls., 1st 24 hrs.
Fresh water _____ feet _____ feet
Salt water 1985 feet _____ feet

Casing and Tubing	Used in Drilling	Left in Well	Packers
Size			Kind of Packer
16			
13			
10	90	90	Size of
8 1/4	1050	None	
6 5/8	1990	1990	Depth set
5 3/16			
3	2639	2639	Perf. top
2			Perf. bottom
Liners Used			Perf. top
			Perf. bottom

CASING CEMENTED _____ SIZE _____ No. Ft. _____ Date _____
COAL WAS ENCOUNTERED AT 555 FEET _____ INCHES
_____ FEET _____ INCHES FEET _____ INCHES
_____ FEET _____ INCHES FEET _____ INCHES

Formation	Color	Hard or Soft	Top	Bottom	Oil, Gas or Water	Depth Found	Remarks
Pittsburgh Coal			555	557			
Big Dunkard			1045	1060			
Gas Sand			1165	1190			
First Salt Sand			1240	1400			
Second Salt Sand			1480	1550			
Maxon			1660	1725			
Big Lime			1844	1870			
Big Injun			1870	2044	show oil & water	1985	
Gants			2185	2275			
Gordon Stray			2599	2616			
Gordon Sand			2618	2634	Gas	2625	
Total Depth				2639			
Mineral Rights owned by:							
S. A. Smith, Agent, Stonewall Jackson Hotel, Clarksburg, W. Va.							
James Dotson, Millstone, W. Va.							
Opal C. Dotson, R.F.D.#1, Central Station, W. Va.							
Esta George, 2728 Minnesota Avenue, S. E., Washington, D. C.							



JUNE 21 1956

McClellan District, Doddridge County, W. Va.

By Carnegie Natural Gas Co., 1015 Frick Bldg., Pittsburgh, 19, Pa.

Abandoned under permit Ded-.....-A7;Quadrangle.

On 100 acres, on Elk Lick Run.

Elevation, 771' L.

Surface owned by Homer E. Ash, Star Route, West Union, W. Va., and minerals by S. A. Smith, Agent, Stonewall Jackson Hotel, Clarksburg, W. Va., James Dotson, Millstone, W. Va., Opal C. Dotson, R. F. D. No. 1, Central Station, W. Va., and Esta George, 2728 Minnesota Ave., S. E., Washington, D. C.

Drilling commenced Sept. 20, 1915; completed Oct. 30, 1915.

Open flow, 14/10ths W. in 6 $\frac{1}{2}$ ".

Volume, 1,443,000 cu. ft.

Rock pressure, 375 lbs.

Salt water at 1985'.

10" casing, 90'; 8 $\frac{1}{4}$ " 1050' (pulled); 6 $\frac{3}{8}$ " 1990' (pulled); 3" tubing, 2639'.

Coal was encountered at 555-557'.

Gas well. Record to Dept. of Mines dated March 15, 1956.

Record to RGT from Mrs. Griffith June 21, 1956. Old File No. 1002.

	Top.	Bottom.
Pittsburgh Coal	555	- 557
Big Dunkard Sand	1045	- 1060
Gas Sand	1165	- 1190
First Salt Sand	1240	- 1400
Second Salt Sand	1480	- 1550
Maxton Sand	1660	- 1725
Big Lime	1844	- 1870
Big Injun Sand (show oil and water, 1985')	1870	- 2044
Gantz Sand	2185	- 2275
Gordon Stray Sand	2599	- 2616
Gordon Sand (gas, 2625')	2618	- 2634
Total depth		2639

AFFIDAVIT OF PLUGGING AND FILLING WELL.

AFFIDAVIT SHOULD BE MADE IN TRIPPLICATE, ONE COPY SHALL GO TO THE DEPARTMENT, ONE COPY TO BE RETURNED BY THE WELL OPERATOR AND THE THIRD COPY AND OTHER COPIES OF RECORDS SHOULD BE MAILED TO STATE COAL OPERATOR AT THEIR RESPECTIVE ADDRESSES.

FORWARD C. Ash

CARNEGIE NATURAL GAS COMPANY

Star Route, West Union, W. Va.

1015 Frick Bldg., Pittsburgh 19, Pa.

James G. Property owner.

May 7, 1956

General Jackson Road, Charleston, W. Va.

WELL AND LOCATION

James Dotson, Hillston, W. Va.

Doddridge

County

Opal C. Dotson, Hillston, W. Va.

Well No. 1 - 532

Central Station, Hillston, W. Va.

D. A. Dotson

Farm

John George, 2720 Minnesota Ave., S.E., Washington, D. C.

Andrew M. Carter

AFFIDAVIT

STATE OF WEST VIRGINIA.

Quantity of Ritchie

and Forrest E. Britton

being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by Carnegie Natural Gas Company, well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 27th day of March, 1956, and that the well was plugged and filled in the following manner:

NAME OR SOURCE RECEIVED	FILLING MATERIAL		PLUGS USED		CHANGES	
	QUANTITY	NO.	SIZE & SHAPE	NO.	DATE	REASON
London etc.	CLAY 2639	2598				
	CEMENT 2598	2598				
Permanent bridge at bridge	CLAY 2074	2074				
	CEMENT 2010	2000				
	CLAY 2000	1850				
	CEMENT 1850	1840				
Permanent bridge at bridge	CLAY 1400	1220				
	CEMENT 1220	1210				
Permanent bridge at bridge	CLAY 630	587				
	CEMENT 587	535				
	CLAY 535	115				
	CEMENT 115	105				
COAL SEALS	CRUSHED STONE 105	100				
	CLAY 100	535				
Permanent bridge at bridge	CEMENT 587	535				
	CLAY 535	30				

and that the work of plugging and filling said well was completed on the 11th day of April, 1956.

Forw'd. H. Britton

Permit No.

(Company)

Address

Location (water)

Well No.

District

The surface of tract is owned by

State

Mineral rights are owned by

Address

Drilling commenced

Drilling completed

Date Shot

With

Open Flow

Volume

Rock Pressure

Oil

Fresh water

Salt water

Formation

Color

Hard or Soft

Top

Bottom

(ft. Gas or Water)

Depth

Feet

Inches

Remarks

Pittsburgh Coal

Big Dunkard

Gas Sand

Red Sandstone

Green Sandstone

Carbonaceous

Big Lime

Clinton

Jantiz

London Gray

London Sand