

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

DATE: NOVEMBER 14th, 2017
API #: 47-061-00328P
Lease No:

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm Name: **GREER STEEL** Operator Well No.: **7114 (Hope 11415) Greer Steel - Plugging (2017)**

LOCATION: Elevation: **1454.27'** Quadrangle: **Masontown**
District: **Morgan** County: **Monongalia**
Latitude: **3.000** Feet South of: **39** Deg. **35** Min. **00** Sec.
Longitude: Feet West of: **79** Deg. **50** Min. **00** Sec.

Well Type: OIL GAS X

Company: **CNX Gas Company LLC** Coal Operator or Owner See List on Page 2
P.O. Box 1248
Jane Lew, WV 26378

Agent: **Christopher Turner**
Permit Issued Date: **5/22/2017**

RECEIVED
Office of Oil and Gas
NOV 16 2017
WV Department of
Environmental Protection

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of **Lewis**

ss:

Steve Spittler and **Mike Lewis** being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 1st day of June, 2017, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Class A Cement - 50 sks	7414'	7047'		
4 1/2" csg			3110'	4327'
6% Gel	7047'	2680'		
Class A Cement - 160 sks	2680'	2316'		
6% Gel	2316'	1600'		
Class A Cement - 195 sks	1600'	1290'		
6% Gel	1290'	700'		
Class A Cement - 200 sks	700'	400'		
6% Gel	400'	300'		
Class A Cement - 179 sks	300'	Surface		
9 5/8" csg				528'
13 3/8" csg				43'


Description of monument: **7" casing extending 48" above Ground Level w/ Company. Well. API & Date Plugged.**

and that the work of plugging and filling said well was completed on the 13th day of June, 2017

And further deponents saith not.

Sworn and subscribe before me this 14th day of Oct, 2017

My commission expires: Sept. 26, 2021



Notary Public

Affidavit reviewed by the Office of Oil and Gas

Haynes J. Knudsen
11/3/2017

Title: INSPECTOR

Created: (9/26/2017)

WR-38
Rev (5-08)
Page 2

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

DATE: **NOVEMBER 14th, 2017**
API #: 47-061-00328P
Lease No:

AFFIDAVIT OF PLUGGING AND FILLING WELL

Farm Name: GREER STEEL

Operator Well No.: 7114 (Hope 11415) Greer Steel - Plugging (2017)

COAL OPERATOR or OWNER

Coal Operator Greer Industries, Inc.
or Owner P.O. Box 1900
Morgantown, WV 26507-1900

Created: (9/26/2017)
Permit Issued Date: 05/22/2017