

STATE OF WEST VIRGINIA  
DEPARTMENT OF ENVIRONMENTAL PROTECTION  
OFFICE OF OIL AND GAS

DATE: January 5<sup>th</sup>, 2015  
API #: 47-061-00394P  
Lease No:

**AFFIDAVIT OF PLUGGING AND FILLING WELL**

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm Name: TENNANT, W. Operator Well No.: 7029 DEPI (Hope 5069) Plugging (2014)

LOCATION: Elevation: 1181.75' Quadrangle: Blacksville  
District: Clay County: Monongalia  
Latitude: 000 Feet South of: 39 Deg. 40 Min. 39 Sec.  
Longitude: 000 Feet West of: 80 Deg. 10 Min. 16 Sec.

Well Type: OIL GAS X

Company: CNX Gas Company LLC Coal Operator or Owner: See List on Page 2  
P.O. Box 1248  
Jane Lew, WV 26378

Agent: Matt Imrich  
Permit Issued Date: 11/21/2014

Received  
Office of Oil & Gas  
JAN 07 2015


**AFFIDAVIT**

STATE OF WEST VIRGINIA,  
County of Lewis ss:

Richard C. Jones and John M. Walsh being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 8th day of December, 2014, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Cement Plug	3003'	2118'	3205' 2" tbg removed prior to	plugging operations.
Gel Plug - 6%	2118'	2028'		90' 2 3/8" work string (stuck in cement).
Cement Plug	2028'	1711'		2177' 5 1/2" csg *
Cement Plug	1711'	1202'		1940' 7" csg *
Cement Plug	1202'	695'		
Cement Plug	695'	Surface		
5 1/2" csg perfed	1990'	57'	4 shots every 50'	
Coal Seam perfed	714'	707'	4 shots per foot	
5 1/2" csg cut @ 2014'				
* 5 1/2" csg cmntd inside of 7"	380'	Surface	To prevent csg removal in order	to properly plug & abandon.

Description of monument: Installed 7" x 6' monument with API # 47-061-00394.  
and that the work of plugging and filling said well was completed on the 15th day of December, 2014.



State of West Virginia deponents saith no.

Cindy L. Kovach  
P.O. Box 454A  
Mt. Clare WV 26408

My Commission Expires September 26, 2021  
subscribed before me this 18th day of December, 2014

My commission expires: SEP. 26, 2021

*[Signatures]*  
Richard C. Jones  
John M. Walsh  
Cindy L. Kovach  
Notary Public  
Title: INSPECTOR  
12/19/2014

Affidavit reviewed by the Office of Oil and Gas

Created: (12/16/2014)

01/09/2015