

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: N. Henderson Operator Well No.: 8201

LOCATION: Elevation: 1197' Quadrangle: Hundred W.VA, PA
District: Battelle County: Monongalia
Latitude: _____ Feet South of 39 Deg. 39 Min. 39.53' Sec.
Longitude: _____ Feet West of -80 Deg. 23 Min. 01.26 Sec.

Well Type: OIL _____ GAS X

Company West Virginia Land Resources, Inc. Coal Operator West Virginia Land Resources, Inc.
1 Bridge Street or Owner 1 Bridge Street
Monongah, WV 26554 Monongah, WV 26554
Agent David Roddy Coal Operator _____
or Owner _____
Permit Issued Date 01/09/2023

AFFIDAVIT


STATE OF WEST VIRGINIA,
County of Monongalia ss:

Matthew A. Yearsley and Kevin S. Wright being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 14th day of February, 2023, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Expandable Cement w/ Gas Blocker	2528'	1722'	5 1/2" Casing - 1730'	748'
Expandable Cement	1722	1221'	7" Casing - 1681"	Unknown
Thixotropic Cement w/ Green Dye	1221'	813'	8 5/8" Casing - 330'	492'
Expandable Cement	813'	Surface	10 3/4" Casing - 0'	274'
			16" Conductor Pipe - 0'	20'

Description of monument: 77" of 7" casing with company name, well #, API #, and date cemented and that the work of plugging and filling said well was completed on the 9th day of March, 2023.

And further deponents saith not. Matthew A. Yearsley
Kevin S. Wright



Sworn and subscribe before me this 27 day of March, 2023.

My commission expires: June 8, 2027 Christopher Willis
Notary Public

Affidavit reviewed by the Office of Oil and Gas: _____ Title: Inspector

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES INC
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address

WEST VIRGINIA LAND RESOURCES INC
Name of Well Operator
1 BRIDGE STREET MONONGAH, WV 26554
Complete Address

WEST VIRGINIA LAND RESOURCES INC
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
RODNEY H. & ROBERT H. KUHN (LIFE BETTY L. KUHN)
Lease or Property Owner
1102 MASON DIXON HWY. BURTON, WV 26562
Address

HUNDRED W.VA, PA
Well Location
BATTELLE
District
MONONGALIA
County
8201
Well No.
N. HENDERSON
Farm

STATE INSPECTOR SUPERVISING PLUGGING _____

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of MONONGALIA ss:

MATTHEW A. YEARSLEY and KEVIN S. WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources Inc. well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 14th day of February, 2023 and that the well was plugged in the following manner:

Sand or Zone Record	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Formation				
Removed 1730' of 5 1/2" casing from the surface to 1730'. Additional attempts to remove the remaining 5 1/2" casing by pulling 150% of the string weight were unsuccessful. Left 748' of 5 1/2" casing in the hole from 1730' to 2478'. Perforated the remaining 5 1/2" casing with 4 shots at each of the following depths; 2378', 2278', 2178', 2078', 1978', 1878' and 1778'. Cleaned a 2 7/8" hole through the 7" and 5 1/2" casing from the surface to 2528'. Cemented the bottom hole from 2528' to 1722' with 105 sacks of Expandable Cement with a Gas Blocker additive. Tagged bottom hole cement plug at 1722'. Removed 1681' of 7" casing from the surface to 1681'. Attempted to remove remaining 7" casing from 1681' by pulling 150% of the string weight but all attempts were unsuccessful. Left an unknown amount of 7" casing in the hole from 1681' to an unknown depth. Cut remaining 7" casing at 1700'. Removed 330' of 8 5/8" casing from 707' to 1037'. Attempted to remove remaining 8 5/8" casing from 1037' by pulling 150% of the string weight were unsuccessful. Left 492' of 8 5/8" casing in the hole from 1037' to 1529'.	5 1/2" Casing 7" Casing 8 5/8" Casing 10 3/4" Casing 16" Conductor	1730' 1681' 330' 0' 0'	748' Unknown 492' 274' 20'	
Coal Seams		Description of Monument		
<u>Pittsburgh</u>	1013.0' - 1020.4'	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 9th day of March, 2023

And further deponents saith not.


Matthew A. Yearsley
Matthew A. Yearsley

Kevin S. Wright
Kevin S. Wright

Sworn to and subscribed before me this 27 day of March 2023

Christopher Andrew Willis
Notary Public

My commission expires:
June 8, 2027



Permit No. 47-061-00407
Well No. 8201
Latitude: 39° 39' 39.53"N
Longitude: -80° 23' 01.26"W

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES INC
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address

WEST VIRGINIA LAND RESOURCES INC
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address

RODNEY H. & ROBERT H. KUHN (LIFE BETTY L. KUHN)
Lease or Property Owner
1102 MASON DIXON HWY. BURTON, WV 26562
Address

WEST VIRGINIA LAND RESOURCES INC
Name of Well Operator
1 BRIDGE STREET MONONGAH, WV 26554
Complete Address

HUNDRED W.VA, PA
Well Location
BATTELLE
District
MONONGALIA
County
8201
Well No.
N. HENDERSON
Farm

STATE INSPECTOR SUPERVISING PLUGGING _____

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of MONONGALIA ss:

MATTHEW A. YEARSLEY and **KEVIN S. WRIGHT** being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources Inc. well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 14th day of February, 2023 and that the well was plugged in the following manner:

Sand or Zone Record	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Formation				
Cut remaining 8 5/8" casing at 1219.4', 1170.4', 1120.4' and 1070.04'. Attempted to remove the 10 3/4" casing from the surface to 274' but all attempts were unsuccessful. Left 274' of 10 3/4" casing in the hole from the surface to 274'. Cut remaining 10 3/4" casing at 180' and 90'. Cleaned a 9 7/8" hole from the surface to the top of the 8 5/8" casing at 1037'. Reduced the hole to 7 7/8" at 1037'. Cleaned a 7 7/8" hole from 1037' to the top of the 7" casing at 1681'. Reduced the hole to 6 1/4" at 1681'. Cleaned a 6 1/4" hole from 1681' to the top of the bottom hole plug at 1722'. Cleaned a 9 7/8" hole through the Pittsburgh Coal Seam (1013.0' - 1020.4'). Left 20' of 16" conductor pipe in the hole from the surface to 20'.	5 1/2" Casing	1730'	748'	
	7" Casing	1681'	Unknown	
	8 5/8" Casing	330'	492'	
	10 3/4" Casing	0'	274'	
	16" Conductor	0'	20'	
Cemented the hole from 1722' to the surface as follows: From 1722' to 1221' with 115 sacks of Expandable Cement. From 1221' to 813' with 170 sacks of Thixotropic Cement with Green Dye and from 813' to the surface with 355 sacks of Expandable Cement. Cement did circulate at the surface. A total of 745 sacks of cement were used to fill the hole from 2528' to the surface.				
Coal Seams		Description of Monument		
Pittsburgh	1013.0' - 1020.4'	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 9th day of March, 2023

And further deponents saith not.

Matthew A. Yearsley
Matthew A. Yearsley

Kevin S. Wright
Kevin S. Wright

Sworn to and subscribed before me this 27 day of March 2023

Christopher Andrew Willis
Notary Public

My commission expires:
June 8, 2027



Permit No. 47-061-00407
Well No. 8201
Latitude: 39° 39' 39.53"N
Longitude: -80° 23' 01.26"W