

(+) DENOTES LOCATION OF WELL ON UNITED STATES TOPOGRAPHIC MAPS

FILE NO. _____
 DRAWING NO. _____
 SCALE 1" = 400'
 MINIMUM DEGREE OF ACCURACY 1 IN 5000
 PROVEN SOURCE OF ELEVATION COMPANY SURVEY TIED INTO U.S.G.S. NETWORK

I THE UNDERSIGNED, HEREBY CERTIFY THAT THIS PLAT IS CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF AND SHOWS ALL THE INFORMATION REQUIRED BY LAW AND THE REGULATIONS ISSUED AND PRESCRIBED BY THE DEPARTMENT OF MINES.
 (SIGNED) R. Nelson McCoy
 R.P.E. _____ L.L.S. 110

PLACE SEAL HERE

STATE OF WEST VIRGINIA
 DEPARTMENT OF MINES
 OIL AND GAS DIVISION



DATE JANUARY 6, 1984
 OPERATOR'S WELL NO. 4260
 API WELL NO. 47-061-0750-P

WELL TYPE: OIL ___ GAS ___ LIQUID INJECTION ___ WASTE DISPOSAL ___
 (IF "GAS,") PRODUCTION ___ STORAGE ___ DEEP ___ SHALLOW X ABANDONED X
 LOCATION: ELEVATION 1158.64 WATERSHED SOUTH FORK OF DUNKARD CREEK
 DISTRICT BATTELLE COUNTY MONONGALIA
 QUADRANGLE MANNINGTON W.V. 7.5
 SURFACE OWNER HARRY M. KING ACREAGE 58.48
 OIL & GAS ROYALTY OWNER UNKNOWN LEASE ACREAGE _____

PROPOSED WORK: DRILL ___ CONVERT ___ DRILL DEEPER ___ REDRILL X FRACTURE OR STIMULATE ___ PLUG OFF OLD FORMATION ___ PERFORATE NEW FORMATION ___ OTHER PHYSICAL CHANGE IN WELL (SPECIFY) _____
 PLUG AND ABANDON ___ CLEAN OUT AND REPLUG X
 TARGET FORMATION NONE ESTIMATED DEPTH _____
 WELL OPERATOR CONSOLIDATION COAL COMPANY DESIGNATED AGENT ROGER E. DUCKWORTH
 ADDRESS P.O. BOX 1314 MORGANTOWN W.V. 26505 ADDRESS P.O. BOX 1314 MORGANTOWN W.V. 26505

OCT 29 1984

FORM IV-6 (8-78) H.T. HALL

COUNTY NAME PERMIT

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Consolidation Coal Company
Coal Operator or Owner
P.O. Box 1314, Morgantown W. Va. 26507-1314

Consolidation Coal Company
Name of Well Operator
P.O. Box 1314, Morgantown, W. Va. 26507-1314

Address
Consolidation Coal Company
Coal Operator or Owner
P.O. Box 1314, Morgantown, W. Va. 26507-1314

December 11, 19 84
WELL AND LOCATION
Battelle District

Address
Harry M. King
Lease or Property Owner

Monongalia County
WELL NO. 4260

Address

Harry M. King Farm

STATE INSPECTOR SUPERVISING PLUGGING

Don Ellie Fairmont, W. Va. 26554

AFFIDAVIT

RECEIVED
DEC 20 1984

STATE OF WEST VIRGINIA,
County of Monongalia

ss:

OIL & GAS DIVISION

Calvin C. Lofton

and Mark Wright

DEPT. OF MINES

being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by Consolidation Coal Company, well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 8th day of November, 19 84, and that the well was plugged and filled in the following manner:

Sand or Zone Record Formation	Filling Material	Plugs Used Size & Kind	Casing	
			CSG PULLED	CSG LEFT IN
Cleaned out wellbore to 1,500 feet.	Pulled 80 feet of 2 7/8 in. tubing			
Could be junk in front of coal	. Pulled 259 feet of 8 1/2 inch casing			
Ran coal protection string as follows: 337.69 feet of 2 3/8 tubing followed by 1,101.56 feet of 4 1/2 inch casing.	Latch down plug at 1,096.56 feet.			
Circulated cement to surface as follows: Pumped 800 sacks of poz mix followed by 235 sacks of expanding cement. Displaced cement to 1,096.56 feet with water. Let set, bailed dry. Total plug 1,439.25 feet.				
Coal Seams				
(Name) Pittsburgh 972 feet	to 980 feet	5 feet of 4 1/2 inch casing with plaque stating: Consol 4260 47-061-0750-P		
(Name)				
(Name)				
(Name)				

Handwritten: 12-19-84

and that the work of plugging and filling said well was completed on the 11th day of December, 19 84.


And further deponents saith not.

Handwritten signatures: Calvin C. Lofton, Mark Wright

Sworn to and subscribed before me this 13th day of December, 19 84.

Handwritten signature: J. R. Everitt
Notary Public

My commission expires:



Permit No. 47-061-0750-P