

*calc 15' loc*  
 1.825  
 0.43W

(+) DENOTES LOCATION OF WELL ON UNITED STATES TOPOGRAPHIC MAPS

FILE NO. \_\_\_\_\_  
 DRAWING NO. \_\_\_\_\_  
 SCALE 1" = 300'  
 MINIMUM DEGREE OF ACCURACY 1 IN 5000  
 PROVEN SOURCE OF ELEVATION COMPANY SURVEY  
TIED INTO U.S.G.S. NETWORK

I THE UNDERSIGNED, HEREBY CERTIFY THAT THIS PLAT IS CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF AND SHOWS ALL THE INFORMATION REQUIRED BY LAW AND THE REGULATIONS ISSUED AND PRESCRIBED BY THE DEPARTMENT OF ENERGY.  
 (SIGNED) *Paul D. Walker*  
 R.P.E. \_\_\_\_\_ L.L.S. 862

PLACE SEAL HERE

STATE OF WEST VIRGINIA  
 DEPARTMENT OF ENERGY  
 OIL AND GAS DIVISION



DATE 2-25, 1994  
 OPERATOR'S WELL NO. MI-471  
 API WELL NO. 47-61-01152-P

WELL TYPE: OIL  GAS  LIQUID INJECTION  WASTE DISPOSAL   
 (IF "GAS,") PRODUCTION  STORAGE  DEEP  SHALLOW  ABANDONED   
 LOCATION: ELEVATION 1355.19 WATERSHED JAKES RUN

DISTRICT CLAY COUNTY MONONGALIA  
 QUADRANGLE BLACKSVILLE WV-PA + 15' WC

SURFACE OWNER BOBBY D. JONES ACREAGE 25.49  
 OIL & GAS ROYALTY OWNER \_\_\_\_\_ LEASE ACREAGE \_\_\_\_\_

PROPOSED WORK: DRILL  CONVERT  DRILL DEEPER  REDRILL  FRACTURE OR STIMULATE  PLUG OFF OLD FORMATION  PERFORATE NEW FORMATION  OTHER PHYSICAL CHANGE IN WELL (SPECIFY) \_\_\_\_\_

PLUG AND ABANDON  CLEAN OUT AND REPLUG   
 TARGET FORMATION NONE ESTIMATED DEPTH \_\_\_\_\_

WELL OPERATOR CONSOLIDATION COAL COMPANY DESIGNATED AGENT ROGER E. DUCKWORTH  
 ADDRESS PO BOX 1314 MORGANTOWN WV 26505 ADDRESS PO BOX 1314 MORGANTOWN WV 26505

FORM WW-6  
 HALLS INC. 068065

COUNTY NAME  
 PERMIT

RECEIVED  
OFFICE OF OIL AND  
GAS  
DEC 02 1996  
WV Division of  
Environmental Protection

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Consolidation Coal Co.  
Coal Operator or Owner  
P.O. Box 1314 Morgantown, WV 26507  
Address

Consolidation Coal Co.  
Coal Operator or Owner  
P.O. Box 1314 Morgantown, WV 26507  
Address

Bobby D. Jones  
Lease or Property Owner  
Rt. 2 Box 72 Fairview, WV 26570  
Address

Consolidation Coal Co.  
Name of Well Operator  
P.O. Box 1314 Morgantown, WV 26507  
Complete Address  
May 26, 19 94

WELL AND LOCATION  
Clay District  
Monongalia County

WELL NO. M1-471  
Jones Farm

STATE INSPECTOR SUPERVISING PLUGGING

AFFIDAVIT

STATE OF WEST VIRGINIA,  
County of Monongalia

ss:

Larry L. Yost

and Dennis L. Yost

being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by Consolidation Coal Co., well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 29th day of April, 19 94, and that the well was plugged and filled in the following manner:

Sand or Zone Record Formation	Filling Material	Plugs Used Size & Kind	Casing	
			CSG PULLED	CSG LEFT IN
	Cleaned Wellbore to 1260 ft.	8 1/4"	95ft.	
	Pulled 95 ft. of 8 1/4 casing	Top	-875 ft.	
	Ran coal protection string as follows; 937 ft. of 4 1/2 casing; 268 ft. of 2 3/8" tubing; Latch down plug at 907 ft; Float Valve at 937 ft; Swedge at 938ft.	Bottom	-?	
	Circulated cement to surface as follows 500 sacks of Poz Mix; 350 sacks of expanding type of cement. 1,000 gal of mud flush. Let Set bailed dry, set monument.			
Coal Seams				Description of Monument
(Name) Pittsburgh 790'	- 800'			6' of 4 1/2 casing with plaque stating Consol M1-471
(Name)				01152 - P
(Name)				
(Name)				


and that the work of plugging and filling said well was completed on the 18th day of May, 19 94.

And further deponents saith not.

Sworn to and subscribed before me this 26th day of MAY, 19 94.

Larry L. Yost  
Dennis L. Yost  
Cheral A. Skinner  
Notary Public

My commission expires:  
MARCH 12, 2002



061  
Permit No. 01152-P

DEC 0 1996