

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Consolidation Coal Company
Coal Operator or Owner
P.O. Box 100, Osage, WV 26543
Address
Consolidation Coal Co.
Coal Operator or Owner
P.O. Box 100, Osage, WV 26543
Address
Freda L. Phillips
Lease or Property Owner
Rt. 1, Box 21, Wadestown, WV 26589
Address

Consolidation Coal Company
Name of Well Operator
P.O. Box 100, Osage, WV 26453
Complete Address
September 22 1997
WELL LOCATION
Battelle
District
Monongalia
County
#4187
WELL NO.
Freda L. Phillips
FARM

STATE INSPECTOR SUPERVISING PLUGGING

[Signature]

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of Harrison

ss:

G. Andrew Lang and Kevin S. Wright
being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by Consolidation Coal Company well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 14th day of August 1997 and that the well was plugged in the following manner:

Sand or Zone Record	Filling Material	Plugs Used	Casing Pulled	Casing Left In
Formation		Size & Kind		
Clean hole with 9 7/8" bit from surface to top of 8 5/8" casing at 849'				
Reduced hole to 7 7/8". Clean 7 7/8" hole from 849' to 1,553'. Pull 8 5/8" casing from 849' to 1,226'. Left 8 5/8" casing in hole from 1,226' to 1,505'. Clean 9 7/8" hole from 849' to 1,226'. Clean 9 7/8" hole thru Pittsburgh coal 1,006' to 1,014'. Ran coal protection string as follows: 99.30' of 2 3/8" tubing followed by 1,434.26' of 4 1/2" casing. Cement hole from 1,533.56' back to surface using 450 sacks of poz mix and 250 sacks of thixotropic cement. Used 1,000 gallons of mud flush. Latch down plug at 1,184.67'. Float valve at 1,225.97'. Swedge at 1,435.26'. Cement did circulate. Displaced cement to 1,184.67' with water let set and bailed dry.		8 5/8"	377'	279'
		16" conductor	0	12'
TOTAL DEPTH: 1,553'				
Coal Seams		Description of Monument		
(Name) Pittsburgh Coal	1,006' to 1,014'	5' of 4 1/2" casing with plaque stating		
(Name)		Consolidation Coal Company Well 4187		
(Name)		Permit #47-61-01259 P		

and that the work of plugging and filling said well was completed on the 26th day of August 1997


And further deponents saith not.

[Signature]

Sworn to and subscribed before me this 25th day of September 1997

[Signature]
Notary Public

My commission expires:
June 29, 1999



Permit No.
47-61-01259 P