



AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

CONSOLIDATION COAL COMPANY  
Coal Operator or Owner  
P. O. BOX 100, OSAGE, WV 26453  
Address  
CONSOLIDATION COAL COMPANY  
Coal Operator or Owner  
1800 WASHINGTON RD, SUITE 2  
Address  
PITTSBURGH, PA. 15241-1407  
Lease or Property Owner  
Address

CONSOLIDATION COAL CO.  
Name of Well Operator  
P.O. BOX 100, OSAGE, WV 26453  
Complete Address  
5-17-97 19  
WELL LOCATION  
BATTELLE  
District  
MONONGALIA  
County  
4180  
WELL NO.  
FARM

STATE INSPECTOR SUPERVISING PLUGGING

*Randee Muck*

AFFIDAVIT

STATE OF WEST VIRGINIA,  
County of HARRISON

ss:

KEVIN WRIGHT

and

G. ANDREW LANG

being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by CONSOLIDATION COAL CO. well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 22ND day of March 1997 and that the well was plugged in the following manner:

Sand or Zone Record	Filling Material	Plugs Used	Casing Pulled	Casing Left In
Formation		Size & Kind		
CLEANED 9 7/8" HOLE TO 533'. WENT DOWN BESIDE 8 5/8" CASING		8 5/8"	265.62'	712'
AT 517'. EXTREME DIFFICULTY GETTING IN 8 5/8" CASING. GOT IN CSG.				
AT 533'. REAMED 12 1/4" HOLE TO 518'. PULLED 8 5/8" CASING TO		16" CONDUCTOR	0	24'
554'. TRIED TO CLEAN OUT 8 5/8" CASING AT 643'. CASING FILLED				
WITH JUNK 8". PULLED 8 5/8" CASING TO 791'. 129' OF THE 8 5/8"		20" CONDUCTOR	0	10"
FULL OF CEMENT. CLEANED 7 7/8" HOLE TO 1502'. CLEANED CEMENT				
AND WOOD PLUG FROM 1094' TO 1102'. CASING CEMENTED ON THE				
OUTSIDE. SECTION MILLED 8 5/8" CASING THRU PITTSBURGH COAL				
FROM 1116' TO 1124'. RAN 4 1/2" COAL PROTECTION STRING TO 1488.82'.				
CEMENTED HOLE FROM 1488.82' TO SURFACE. LATCH DOWN.				
PLUG AT 1284.33'. FLOAT VALVE AT 1309.58'. CEMENT DID				
CIRCULATED. USED 1000 GALLONS OF MUD FLUSH. DISPLACED				
CEMENT TO 1284.33' WITH WATER. LET SET AND BAILED DRY.				
TOTAL DEPTH: 1,502 FEET				
Coal Seams		Description of Monument		
(Name) PITTSBURGH	1116' TO 1124'	5' OF 4 1/2" CASING		
(Name)		WITH PLAQUE STATING		
(Name)		CONSOLIDATION COAL CO.		
(Name)		WELL #4180 PERMIT 47-61-1270-P		


and that the work of plugging and filling said well was completed on the 05TH day of April 1997

And further deponents saith not.

*Kevin S. Wright*  
*G. Andrew Lang*

Sworn to and subscribed before me this 17TH day of May 1997

My commission expires: 6-29-99



*Charlotte Hooper*  
Notary Public  
Permit No. 47-61-1270-P

007 24 1997