

WR-38  
DATE: August 26, 2000

API # 47-061-01391

STATE OF WEST VIRGINIA  
DIVISION OF ENVIRONMENTAL PROTECTION  
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Roy D. Chisler Operator Well No.: F2-445

LOCATION: Elevation: 1240 Quadrangle: Wadestown  
District: Battelle County: Monongalia  
Latitude: 550 Feet South of 39 Deg. 40 Min. 00 Sec.  
Longitude: 5000 Feet West of 80 Deg. 17 Min. 30 Sec.

Well Type: OIL  GAS

Company: Eastern Associated Coal Corp Coal Operator Eastern Associated Coal Corp.  
1044 Miracle Run Road or Owner 1044 Miracle run Road  
Fairview, WV 26570 Fairview, WV 26570

Agent: Terry O. hendershot Coal Operator \_\_\_\_\_  
or Owner \_\_\_\_\_

Permit Issued Date: June 16, 2000

AFFIDAVIT

STATE OF WEST VIRGINIA,  
County of Monongalia ss:

Craig Park and Bill Chisler being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well, and Randall Mick Oil and Gas Inspector representing the Director, say that said work was commenced on the 16 day of June, 2000, and that the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Cleaned out	to a depth of 1600'			
Logged well	gamma Ray, Neutron, and 3 Caliper Arm.			
Ripped old 8"	from 1030'	to 1060'	Run 2" tubing to 1600'	run 10 sks gell & 110 sks portland.
Run 4 1/2" pipe	1218'	Run 650 sks portland	and 110 sks expandable cement,	pump.
Plug to 1130'	Bailed water out inside 4 1/2" & checked plug. OK			
Pittsburgh Coal	1042 to 1050			

*[Handwritten signature]* 10/29/02

Description of monument: 4 1/2" pipe metal plate A.P.T.# and date plugged and that the work of plugging and filling said well was completed on the 14 day of July, 2000.

And further deponents saith not.

Craig Park


Bill Chisler

Sworn and subscribe before me this 28th day of August  
My commission expires: January 13, 2003

Allen K Moore

Notary Public

Oil and Gas Inspector: Randall Mick



MONO 1391