

STATE OF WEST VIRGINIA  
DIVISION OF ENVIRONMENTAL PROTECTION  
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Betty Baird Operator Well No.: F2-466

LOCATION: Elevation: 1002 Quadrangle: Wadestown  
District: Battelle County: Monongalia  
Latitude: 8900 Feet South of 39 Deg. 40 Min. 00 Sec.  
Longitude: 1100 Feet West of 80 Deg. 17 Min. 30 Sec.

Well Type: OIL X GAS \_\_\_\_\_

Company: Eastern Associated Coal Corp. Coal Operator Eastern Associated Coal Corp.  
1044 Miracle Run Road or Owner 1044 Miracle Run road  
Fairview, W. Va. 26570 Fairview, W.Va. 26570

Agent: Terry O. Hendershot Coal Operator \_\_\_\_\_  
or Owner \_\_\_\_\_

Permit Issued Date: September 8, 2000

AFFIDAVIT

STATE OF WEST VIRGINIA,  
County of Monongalia ss:

Jeff Hostuttler and Craig Park being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well, and Randall Mick Oil and Gas Inspector representing the Director, say that said work was commenced on the 8th day of September, 2000, and that the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Cleaned out to depth of 1627'				
Logged well gamma Ray, Neutron & 3 Arm Caliper				
Run 1 1/2" tubing to 1620 .	Run 5 sks gel &	223 sks Portland &	pulled tubing.	
Run 4 1/2" pipe to 898.	Run 550 sks portland &	110 sks Chem Comp		
Pumped Latch down plug to	878. Old 8" pipe From	936' to 1420'		
Bailed water out inside 4 1/2" pipe &	Checked plug.	O.K.		
Pittsburgh Coal 800 to 808				


RECEIVED  
Office of Oil and Gas  
November 18, 2000  
WV Department of Environmental Protection

Description of monument: 4 1/2" pipe Metal Plate A.P.I. # & Date Plugged and that the work of plugging and filling said well was completed on the 27 day of October, 2000

And further deponents saith not. Jeffery Hostuttler  
Craig Park

Sworn and subscribe before me this 29th day of November, 2000  
My commission expires: January 13, 2003  
Allen K Moore  
Notary Public

Oil and Gas Inspector: Randall Mick



MONO 1394 P