

DATE: November 23, 2000

STATE OF WEST VIRGINIA
DIVISION OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Kyle Howard Operator Well No.: F2-459

LOCATION: Elevation: 1297' Quadrangle: Wadestown
District: Battelle County: Monongalia
Latitude: 5025' Feet South of 39 Deg. 40 Min. 00 Sec.
Longitude: 1700' Feet West of 80 Deg. 17 Min. 30 Sec.

Well Type: OIL X GAS _____


Company: Eastern Associated Coal Corp. Coal Operator Eastern Associated Coal Corp.
1044 Miracle Run Road or Owner 1044 Miracle Run Road
Fairview, W. Va. 26570 Fairview, W. Va. 26570

Agent: Terry O. Hendershot Coal Operator _____
or Owner _____

Permit Issued Date: October 17, 2000

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of Monongalia ss:



Jeff Hostuttler and Craig Park being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well, and Randall Mick Oil and Gas Inspector representing the Director, say that said work was commenced on the 13th day of October, 2000, and that the well was plugged and filled in the following manner:


TYPE	FROM	TO	PIPE REMOVED	LEFT
Cleaned out	to deapth of	1410'		
Logged well	Gamma ray Neutron & 3 Arm Claiper.			
Run 4 1/2" pipe	to 1400'. Run 10 sks gel.			
Run 1290 sks	Portland & 140 sks Chem comp			
Pumped latch	down plug to	1123'		
Bailed water	out inside 4 1/2" pipe & checked plug O.K.			
Pittsburg Coal	1035' to	1043'		

Description of monument: 4 1/2" pipe Metal Plate A.P.I. # & Date Plugged and that the work of plugging and filling said well was completed on the 14 day of November, 2000.

And furthur deponents saith not. Jeffery Hostuttler
Craig Park

MAR 26 2004

Sworn and subscribe before me this 29th day of November, 2000
My commission expires: January 13, 2003
Allen K Moore
Notary Public



Oil and Gas Inspector: Randall Mick

MONO 1396