

STATE OF WEST VIRGINIA  
DEPARTMENT OF ENVIRONMENTAL PROTECTION  
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Thomas Marshall Operator Well No.: F2-477

LOCATION: Elevation: 1,116 (surveyed) Quadrangle: Wadestown  
District: Battelle County: Monongalia  
Latitude: 2,850 Feet South of 39 Deg. 40 Min. 00 Sec.  
Longitude: 5,650 Feet West of 80 Deg. 17 Min. 30 Sec.


Well Type: OIL X GAS \_\_\_\_\_

Company: Eastern Associated Coal Corp Coal Operator: Eastern Associated Coal Corp  
1044 Miracle Run Road or Owner 1044 Miracle Run Road  
Fairview, WV 26570 Fairview, WV 26570

Agent: Edward Y. Hoy

Coal Operator: \_\_\_\_\_  
or Owner \_\_\_\_\_

Permit Issued Date: July 26, 2001



AFFIDAVIT

STATE OF WEST VIRGINIA,  
County of Monongalia ss:

Michael Hayhurst and David Chisler being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well, and Randall Mick Oil and Gas Inspector representing the Director, say that said work was commenced on the 2<sup>nd</sup> day of August, 2001, and that the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
	Cleaned out to 1,428 ft.			
	Logged well—Gamma Ray, CCL and 3-arm caliper.			
	Ran 1½" tubing to 1,420 and pumped 75 sacks of cement. Pulled 1½" tubing. Ripped 7" casing from 885' – 915'. Ran tubing back in and pumped 40 sacks.			
	Ran 4 ½" pipe with latch down plug to 1,031' and pump 3 gel and 80 sacks cement.			
	Ran 1½" tubing outside 4" pipe to 698 ft., where cement was tagged - pumped 40 sacks EaK cement and 685 sacks cement back to surface			
	Pulled 1½" tubing.			
	Bailed water out of the inside of 4½" pipe and checked plug—OK.			
	Pittsburgh Coal: 882 - 889			


Description of monument: 4½" Pipe with metal plate, API#, Date plugged and that the work of plugging and filling said well was completed on the 30<sup>th</sup> day of August 2001.

And further deponents saith not.

Michael Hayhurst  
David Chisler

Sworn and subscribe before me this 20<sup>th</sup> day of SEPTEMBER 2001.  
My commission expires: JULY 7, 2007

[Signature]  
Notary Public



MOND 1413-P