

STATE OF WEST VIRGINIA
 DEPARTMENT OF ENVIRONMENTAL PROTECTION
 OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Albert & Bessie Roupe, etal. Operator Well No.: F2-478


LOCATION: Elevation: 1,407' Quadrangle: Wadestown
 District: Batelle County: Monongalia
 Latitude: 5,600 Feet South of 39 Deg. 40 Min. 00 Sec.
 Longitude: 7,750 Feet West of 80 Deg. 17 Min. 30 Sec.

Well Type: OIL X GAS _____

Company: Eastern Associated Coal Corp. Coal Operator Eastern Associated Coal Corp.
1044 Miracle Run Road or Owner 1044 Miracle Run Road
Fairview, WV 26570 Fairview, WV 26570

Agent: Edward Y. Hoy Coal Operator or Owner _____

Permit Issued Date: July 26, 2001



AFFIDAVIT

STATE OF WEST VIRGINIA,
 County of Monongalia ss:

Michael Huxhurst and Jeff Sine being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well, and Steve Mosser, Oil and Gas Inspector representing the Director, say that said work was commenced on the 2nd day of August, 2001, and that the well was plugged and filled in the following manner:


TYPE	FROM	TO	PIPE REMOVED	LEFT
Clean out with 12" bit to 242', Clean out with 9 7/8" bit to 1159', Clean out to 1555' with 7" bit.				
Logged hole with Timco(Gamma Ray CCL and Caliper)				
Pumped bottom plug with 95 sacks of cement.				
Perforated 8" casing from 1185' to 1220'.				
Ran 1303' of 4 1/2" pipe to 1303' with latch down plug. Pumped 840 sacks of cement and 105 sacks of E1K cement.				
Checked top of latch down plug at 1296'. Topped hole off with 27 sacks of cement.				
Downhole survey by Sperry-Sun on 7-11-02.				
Pittsburgh coal- 1196'-1203'				

Description of monument: 4 1/2" Pipe with metal plate, API #, and date plugged and that the work of plugging and filling said well was completed on the 8th day of July, 2002.

And further deponents saith not. X Michael Huxhurst
X Jeff Sine

Sworn and subscribe before me this 29th day of AUGUST, ~~2002~~ 2002
 My commission expires: JULY 7, 2007

[Signature]
 Notary Public
 Oil and Gas Inspector: [Signature]



MONO 1414P