

STATE OF WEST VIRGINIA  
DEPARTMENT OF ENVIRONMENTAL PROTECTION  
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Nova Sheets Operator Well No.: F2-479

LOCATION: Elevation: 1,488 (surveyed) Quadrangle: Wadestown  
District: Battelle County: Monongalia  
Latitude: 5,600 Feet South of 39 Deg. 40 Min. 00 Sec.  
Longitude: 8,175 Feet West of 80 Deg. 17 Min. 30 Sec.


Well Type: OIL X GAS \_\_\_\_\_

Company: Eastern Associated Coal Corp Coal Operator: Eastern Associated Coal Corp  
1044 Miracle Run Road or Owner 1044 Miracle Run Road  
Fairview, WV 26570 Fairview, WV 26570

Agent: Edward Y. Hoy

Coal Operator:  
or Owner \_\_\_\_\_

Permit Issued Date: August 23, 2001



AFFIDAVIT

STATE OF WEST VIRGINIA,  
County of Monongalia ss:

MICHAEL HAYHURST and CHRIS THOMAS being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well, and Randall Mick Oil and Gas Inspector representing the Director, say that said work was commenced on the 5<sup>th</sup> day of September, 2001, and that the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
	Cleaned out with 12" bit to 254 feet - hit iron.			
	Cleaned out with 7 7/8" bit (inside 8 5/8" casing) to 1603 feet.			
	Ran downhole survey with Javins.			
	Ran 1,600' of 1 1/2" tubing and pumped 2 sacks gel and 700 sacks of cement.			
	Drilled out cement with 7 3/4" hammer bit to 1,330'. Ran 1,330 of 4 1/2" pipe and cement with 320 sacks.			
	Latch down plug @ 1,288'			
	Bailed water out of the inside of 4 1/2" pipe and checked plug—OK.			
<input checked="" type="checkbox"/>	Pittsburgh Coal: 1,283 - 1,290			


Description of monument: 4 1/2" Pipe with metal plate, API#, Date plugged and that the work of plugging and filling said well was completed on the 24<sup>th</sup> day of October 2001.

And further deponents saith not. Michael Hayhurst  
Chris Thomas

Sworn and subscribe before me this 26<sup>th</sup> day of October 20 01.  
My commission expires: July 7, 2007

Edward Y. Hoy  
Notary Public

Oil and Gas Inspector: Randall Mick



MONO 1416P 8-917