

STATE OF WEST VIRGINIA  
DEPARTMENT OF ENVIRONMENTAL PROTECTION  
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Eastern Associated Coal Corp Operator Well No.: F2-475

LOCATION: Elevation: 1,275 (surveyed) Quadrangle: Wadestown  
District: Battelle County: Monongalia  
Latitude: 4,475 Feet South of 39 Deg. 40 Min. 00 Sec.  
Longitude: 5,800 Feet West of 80 Deg. 17 Min. 30 Sec.

Well Type: OIL X GAS \_\_\_\_\_

Company: Eastern Associated Coal Corp Coal Operator: Eastern Associated Coal Corp  
1044 Miracle Run Road or Owner 1044 Miracle Run Road  
Fairview, WV 26570 Fairview, WV 26570


Agent: Edward Y. Hoy Coal Operator: \_\_\_\_\_  
or Owner \_\_\_\_\_

Permit Issued Date: 11-19-01

AFFIDAVIT

State of West Virginia,  
County of Monongalia ss:

Michael Hayburn and Gary C Thomas being first duly sworn according to law, depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well, and Randall Mick Oil and Gas Inspector representing the Director, say that said work was commenced on the 18<sup>th</sup> day of December, 2001, and that the well was plugged and filled in the following manner:



TYPE	FROM	TO	PIPE REMOVED	LEFT
Cleaned out with 6 1/2" bit to 1,480'				
Cemented bottom with 76 sacks				
Tagged bottom plug at 1,210				
Ran logs with Timco and Sperry-Sun				
Ran 1,208' of 4 1/2" vent pipe with latch down plug - Pumped 114 sacks of E1K cement and 800 sacks of Portland cement				
Bailed water out of the inside of 4 1/2" pipe and checked plug at 1,151' - OK.				
Pittsburgh Coal: 1,048 - 1,055				

Description of monument: 4 1/2" Pipe with metal plate, API#, Date plugged and that the work of plugging and filling said well was completed on the 17<sup>th</sup> day of January, 2002.

And further deponents saith not. Michael Hayburn  
Gary C Thomas

Sworn and subscribe before me this 1<sup>st</sup> day of February 20 02.  
My commission expires September 28<sup>th</sup> 2004.

Mark Allen Gouzd  
Notary Public  
Randall Mick

Oil and Gas Inspector: \_\_\_\_\_



OFFICIAL SEAL  
NOTARY PUBLIC  
STATE OF WEST VIRGINIA  
MARK ALLEN GOUZD  
Route 3, Box 209-A  
Mannington, West Virginia 26040

MONO 1426-P

MAR 26 2004