



02 09 08:43p
 JUL 27 2009 7:40AM
 rev (9-07)
 -WR-3a
 DATE: 07-22-2009

tristan jenkins
 1044 MIRACLE RUN RD

3046220100

P. 1

API # 47-061-1533P

61-01533P

STATE OF WEST VIRGINIA
 DEPARTMENT OF ENVIRONMENTAL PROTECTION
 OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Fox/McCoy Operator Well No.: E2-42

LOCATION: Elevation: 1,405' Quadrangle: Blacksville
 District: Clay County: Monongalia
 Latitude: 39.955 Feet South of 39 Deg. 42 Min. 30 Sec.
 Longitude: 8.944 Feet West of 89 Deg. 12 Min. 30 Sec.

Well Type: OIL X GAS

Company: Eastern Associated Coal LLC Coal Operator Eastern Associated Coal LLC
1044 Miracle Run Road or Owner 1044 Miracle Run Road
Fairview, WV 26570 Fairview, WV 26570

Agent: Edward Y. Hoy Coal Operator or Owner

Permit issued Date: 10/23/2006
 Renewed 04/29/2009

AFFIDAVIT

STATE OF WEST VIRGINIA,
 County of Monongalia ss:

William S. Storkling and Edward Y. Hoy being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well, and Tristan Jenkins, Oil and Gas Inspector representing the Director, say that said work was commenced on the 19 of April, 2009, and that the well was plugged and filled in the following manner:


TYPE	FROM	TO	PIPE REMOVED	LEFT
Cleared out with a 8" bit down to 1393'.				
A Gamma Ray and Caliper Log was performed on the hole by Century Wireline Services. Based on these logs there is 10" pipe from 906 ft deep to below coal seam, and 8" pipe from 1054 feet down to 1390. Based on the log, the coal depth is between 1056' to 1062'. The 10" was cut at the coal seam and perforated above the coal.				
Ran 1-1/2" tubing down and pumped in the bottom plug with 65 Sacks of ETK expanding cement.				
Tagged bottom plug at 1185'. Ran 1185' of 4-1/2" casing with latchdown plug.				
Pumped the top plug with 1385 sack of ETK expanding cement				
The latchdown plug was tagged at 1155'.				

Description of monument: 4 1/2" Pipe with metal plate with the API # and that the work of plugging and filling said well was completed on the 22nd day of June, 2009.

And further deponents saith not.
William S. Storkling
Edward Y. Hoy

Sworn and subscribe before me this 26th day of July, 2009.
 My commission expires: July 7, 2017

Edward Y. Hoy
 Notary Public
 Oil and Gas Inspector: Tristan Jenkins 3 AUG 09



RECEIVED
 Office of Oil & Gas

JUN 12 2012

WV Department of
 Environmental Protection

06/22/2012