

Rev (5-01)
WR-38
DATE: 05-29-08

API # 47-061-01549P

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: A. McFeater tract, 2 ac., current owner- Sandra Bleigh Operator Well No.: F2- 126

LOCATION: Elevation: 1,293' Quadrangle: Blacksville
District: Clay County: Monongalia
Latitude: 7,498 Feet South of 39 Deg. 42 Min. 30 Sec.
Longitude: 7,586 Feet West of 80 Deg. 12 Min. 30 Sec.

Well Type: OIL GAS

Company: Eastern Associated Coal LLC Coal Operator Eastern Associated Coal LLC
1044 Miracle Run Road or Owner 1044 Miracle Run Road
Fairview, WV 26570 Fairview, WV 26570

Agent: Edward Y. Hoy Coal Operator or Owner _____

Permit Issued Date: June 1, 2007

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of Monongalia ss:

Michael Hayhurst and Charles Price being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well, and Bill Hatfield, Oil and Gas Inspector representing the Director, say that said work was commenced on the 15th day of February, 2008, and that the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
	Cleaned out to 394' with an 8" bit. Cleaned out to 950' with a 6-1/4" bit. Ran a string of 8" casing to 318' to minimized caving problems. Cleaned out to 1,260' with a 6" bit. Got out 413' of 2" tubing, 27' of 10" casing, and 39' of 13" surface casing.			
	Logged the hole with Century Geophysical. Coal seam at 947' to 954' based on log information. No casing through the coal seam.			
	Ran 1-1/2" tubing and pumped the bottom plug with 35 sacks of E1K expanding cement.			
	Tagged bottom plug at 1,060'. Ran 1,065' of 4-1/2" casing with latchdown plug at 1,060'.			
	Pumped the top plug with 656 sacks of E1K expanding cement.			
	Swabbed water off latchdown plug at 1,042'.			


Description of monument: 4 1/2" Pipe with metal plate, API #, and date plugged and the work of plugging and filling said well was completed on the 22nd day of May, 2008.

And further deponents saith not. Michael Hayhurst
Charles Price

Sworn and subscribe before me this 30th day of May, 2008
My commission expires: July 7, 2017

Notary Public

Oil and Gas Inspector: [Signature]



RECEIVED
Office of Oil & Gas
JUN 12 2012

WV Department of
Environmental Protection

06/22/2012