

STATE OF WEST VIRGINIA  
DEPARTMENT OF ENVIRONMENTAL PROTECTION  
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: SIX, RALPH & BETTY JO Operator Well No.: SC-1 (Production)

LOCATION: Elevation: 1192.02' Quadrangle: WADESTOWN, PA 7.5"

District: BATTELLE County: MONONGALIA

Latitude: \_\_\_\_\_ Feet South of 39 Deg. 40 Min. 00 Sec.

Longitude: \_\_\_\_\_ Feet West of 80 Deg. 20 Min. 00 Sec.

Well Type: OIL \_\_\_\_\_ GAS X

Company WEST VIRGINIA LAND RESOURCES, INC. Coal Operator WEST VIRGINIA LAND RESOURCES, INC.  
46226 NATIONAL ROAD WEST or Owner 1 BRIDGE STREET MONONGAH, WV 26554  
ST. CLAIRSVILLE, OH 43950

Agent David Roddy Coal Operator \_\_\_\_\_  
Permit Issued Date 4/26/2022 or Owner \_\_\_\_\_

AFFIDAVIT


STATE OF WEST VIRGINIA,  
County of MONONGALIA ss:

Matthew A. Yearsley and Kevin S. Wright being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 16th day of May, 2022 and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Ploymer Gel	967'	Laterals		
7" Casing	1265.5'	Surface	None	749.3'
9 5/8" Casing	360'	Surface	None	360'
13 3/8" Casing	41'	Surface	None	41'

Description of monument: 77" of 7" casing with company name, well #, API#, and date cemented and that the work of plugging and filling said well was completed on the 17th day of May, 2022.

And further deponents saith not. Kevin S. Wright  
Matthew A. Yearsley



Sworn and subscribe before me this 17th day of Jun, 2022

My commission expires: 09/15/22 Thomas J. Sullivan  
Notary Public

Affidavit reviewed by the Office of Oil and Gas: \_\_\_\_\_ Title: \_\_\_\_\_



AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES, INC.  
Coal Operator or Owner  
46226 NATIONAL ROAD WEST ST. CLAIRSVILLE, OH 43950  
Address  
WEST VIRGINIA LAND RESOURCES, INC  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address  
SIX, RALPH & BETTY JO  
Lease or Property Owner  
11023 Mason Dixon Hwy Burton, WV 26562  
Address

WEST VIRGINIA LAND RESOURCES, INC.  
Name of Well Operator  
1 BRIDGE STREET MONONGAH, WV 26554  
Complete Address  
WADESTOWN, PA 7.5"  
Well Location  
BATTELLE  
District  
MONONGALIA  
County  
SC-1  
Well No.  
SIX, RALPH & BETTY JO  
Farm

STATE INSPECTOR SUPERVISING PLUGGING \_\_\_\_\_

AFFIDAVIT


STATE OF WEST VIRGINIA,  
County of MONONGALIA ss:  
Kevin S. Wright and MATTHEW A. YEARSLEY being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources, Inc. well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 17th day of May, 2022 and that the well was plugged in the following manner:

Sand or Zone Record Formation	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Logged production hole with Caliper and Gamma logs to a total depth of 1121'. (Set down on hole fill). Attempted to remove 7" casing by pulling 150% of string weight. All attempts were unsuccessful. Set bottom plug from 1030' to 888' with 30 sacks of Thixotropic cement. Set 7" packer at 807' and pumped 7,014 gallons of cement or 156% of the total calculated volume into the laterals through the coal seam, access hole to bridge plug, production hole from bottom hole plug to packer until cement was visible at all four laterals. Released 7" packer and cemented the hole from 807' to the surface with 95 sacks of Expandable cement. Cement did circulate at the surface. Left 1116' of 7" casing from the surface to 1116' with 7" Fiberglass from 836' to 893' through the Pittsburgh Coal Seam (871.5' - 878'). Left 351' of 9 5/8" casing from surface to 351'.		7" Steel Casing	0'	1053'
		7" Fiberglass Casing	0'	63'
		9 5/8" Steel Casing	0'	351'
<b>Coal Seams</b> <u>Pittsburgh</u>	<b>(1019' - 1026')</b>	<b>Description of Monument</b>		

... and that the work of plugging and filling said well was completed on the 19th day of May 22, 2022

And further deponents saith not.

Kevin S. Wright  
Kevin S. Wright  
Matthew A. Yearsley  
Matthew A. Yearsley



Sworn to and subscribed before me this 13<sup>th</sup> day of JUN, 2022

[Signature]  
Notary Public

My commission expires: 09/15/22

Permit No. 47-061-01566  
Well No. SC-1  
Latitude: 39° 40' 00"N  
Longitude: 80° 20' 00"W