



13 09 07:35a
JUL 10 2009 12:20PM
WR-38
DATE: 03-09-2009

cristan jenkins
CALL REVENUE RV 2

3046220180

P.1

API # 47-001-1696P

61-01586P

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Carson, Rex Operator Well No.: E2-944

LOCATION: Elevation: 1,345' Quadrangle: Blacksville
District: Clay County: Monongalia
Latitude: 9,372' Feet South of 39 Deg. 42 Min. 30 Sec.
Longitude: 5,385' Feet West of 80 Deg. 12 Min. 30 Sec.

Well Type: OIL ___ GAS ___ X ___

Company: Eastern Associated Coal LLC Coal Operator Eastern Associated Coal LLC
1044 Miracle Run Road or Owner 1044 Miracle Run Road
Fairview, WV 26570 Fairview, WV 26570

Agent: Edward Y. Hoy

Coal Operator
or Owner

Permit Issued Date: Oct 24, 2008

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of Monongalia ss:

Edward Y. Hoy and William J. Stoneking being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well, and Tristan Jenkins, Oil and Gas Inspector representing the Director, say that said work was commenced on the 12th day of March, 2008, and that the well was plugged and filled in the following manner:


TYPE	FROM	TO	PIPE REMOVED	LEFT
Cleaned out with a 10" bit down to 841'. Cleaned out with an 8" bit down to 1335'.				
A Gamma Ray and Caliper Log was performed on the hole by Timco, INC. Based on these logs there is 13" pipe from 64 feet deep to 177 feet deep, and 10" pipe from 513 feet down to below the coal seam. Deviation log was ran by Century Wireline Services. Based on the log, the coal depth is between 999' and 1008'.				
Ran 1+1/2" tubing down and pumped in the bottom plug with 90 Sacks of E1K expanding cement.				
Tagged bottom plug at 1,111'. Ran 1114' of 4-1/2" casing with hatchdown plug.				
Pumped the top plug with 620 sack of E1K expanding cement.				
The hatchdown plug was tagged at 1104'.				

Description of monument: 4 1/2" Pipe with metal plate with the API # and that the work of plugging and filling said well was completed on the 9th day of April, 2009.
And further deponents saith not.

Sworn and subscribe before me this 10th day of July
My commission expires: July 7, 2017

Notary Public

Oil and Gas Inspector: [Signature]



RECEIVED

Office of Oil & Gas

JUN 12 2012

WV Department of
Environmental Protection

06/22/2012