

STATE OF WEST VIRGINIA  
 DEPARTMENT OF ENVIRONMENTAL PROTECTION  
 OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Tennant, Norris Operator Well No.: E2-41

LOCATION: Elevation: 1,221 Quadrangle: Blacksville

District: Clay County: Monongalia  
 Latitude: 8.149 Feet South of 39 Deg. 42 Min. 30 Sec.  
 Longitude: 5.671 Feet West of 80 Deg. 12 Min. 30 Sec.

Well Type: OIL X GAS

Company: Eastern Associated Coal LLC Coal Operator: Eastern Associated Coal LLC  
1044 Miracle Run Road or Owner: 1044 Miracle Run Road  
Fairview, WV 26570 Fairview, WV 26570

Agent: Edward Y. Hoy Coal Operator or Owner

Permit Issued Date: January 29, 2009

STATE OF WEST VIRGINIA,  
 County of Monongalia ss:

AFFIDAVIT [Signature] 12 Feb 09

Jeff Sise and Gracelynn Hickman being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well, and Tristan Jenkins, Oil and Gas Inspector representing the Director, say that said work was commenced on the 29<sup>th</sup> day of June, 2009, and that the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
	Cleaned out with 12" bit to 357'	Cleaned out with 8 3/4" bit to 1200'		
	Logged the hole with Century Wireline Service. Coal seam 870' to 877' based on log information. The hole deviated 6.9 feet at the coal seam. There is 10" casing from 388' to below the coal seam. The pipe was shot at and above the coal seam by Timco Inc.			
	Ran 1-1/2" tubing and pumped the bottom plug with 80 sacks of ETK expanding cement. The top of the bottom plug is 980' deep.			
	Ran 977.5' of 4-1/2" tubing and pumped the top plug with 320 sacks of ETK expanding cement. Swabbed water off hole. Latch down plug at 958'.			


Description of monument: 4 1/2" Pipe with metal plate, API #, and date plugged and that the work of plugging and filling said well was completed on the 2<sup>nd</sup> day of July, 2009.

And further deponents saith not.

Sworn and subscribe before me this 2<sup>nd</sup> day of FEBRUARY, 2010  
 My commission expires: \_\_\_\_\_

Oil and Gas Inspector:

[Signature] Notary Public  
12 Feb 09



RECEIVED  
 Office of Oil & Gas

JUN 18 2012

WV Department of  
 Environmental Protection

06/22/2012