

Rev (5-01)  
WR-38  
DATE: 04-14-10

API # 47-6101594P

61-01594P

STATE OF WEST VIRGINIA  
DEPARTMENT OF ENVIRONMENTAL PROTECTION  
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Tennant, Norris Operator Well No.: FZ-127

LOCATION: Elevation: 1,369 Quadrangle: Blacksville  
District: Clay County: Monongalia  
Latitude: 7.892' Feet South of 39 Deg. 42 Min. 30 Sec.  
Longitude: 6.841' Feet West of 80 Deg. 12 Min. 30 Sec.

Well Type: OIL  GAS

Company: Eastern Associated Coal LLC Coal Operator: Eastern Associated Coal LLC  
1044 Miracle Run Road or Owner: 1044 Miracle Run Road  
Fairview, WV 26570 Fairview, WV 26570

Agent: Edward Y. Hoy Coal Operator or Owner: \_\_\_\_\_

Permit Issued Date: February 3, 2009

AFFIDAVIT

STATE OF WEST VIRGINIA,  
County of Monongalia ss:

Jeff Sine and Garrett Hickman being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well, and Tristan Jenkins, Oil and Gas Inspector representing the Director, say that said work was commenced on the 7<sup>th</sup> day of July, 2009, and that the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
	Cleaned out with 12" bit to 225'. Cleaned out with 7" bit to 1230'. Cleaned out with a 6 1/2" bit to 1410'.			
	Logged the hole with Century Wireline Service. Coal seam 1018' to 1025' based on log information. The hole deviated 13.8 feet at the coal seam. There is 8" casing from 226' to 1226'. There is 7" casing from 1226' to 1410'. The pipe was shot at and above the coal seam by Timco Inc.			
	Ran 4-1/2" tubing and pumped the bottom plug with 55 sacks of E1K expanding cement. The top of the bottom plug is 1140' deep.			
	Ran 1140' of 4-1/2" casing and pumped the top plug with 230 sacks of E1K expanding cement by BJ Hughes. Swabbed water off hole. Latch down plug at 1123'.			

Description of monument: 4 1/2" Pipe with metal plate, API #, and date plugged and that the work of plugging and filling said well was completed on the 24<sup>th</sup> day of July, 2009.

And further deponents saith not. Jeff Sine


Garrett Hickman

Sworn and subscribe before me this 14<sup>th</sup> day of April, 2009

My commission expires: July 7, 2017

Notary Public

Oil and Gas Inspector: \_\_\_\_\_



RECEIVED  
Office of Oil & Gas

JUN 12 2012

WV Department of  
Environmental Protection