

Rev (5-01)
WR-38
DATE: 08-05-12

API # 47-6101628P

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Derrah, Edith Operator Well No.: F2- S17A
LOCATION: Elevation: 1,498' Quadrangle: Blacksville
District: Clay County: Monongalia
Latitude: 14.062' Feet South of 39 Deg. 40 Min. 00 Sec.
Longitude: 8.434' Feet West of 80 Deg. 12 Min. 30 Sec.
Well Type: OIL X GAS _____
Company: Eastern Associated Coal LLC Coal Operator: Eastern Associated Coal LLC
1044 Miracle Run Road or Owner 1044 Miracle Run Road
Fairview, WV 26570 Fairview, WV 26570
Agent: Edward Y. Hoy Coal Operator _____
or Owner _____
Permit issued Date: May 24, 2011

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of Monongalia ss:

X Kenneth Gump and Garrett Hickman being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well, and Sam Ward, Oil and Gas Inspector representing the Director, say that said work was commenced on the 29th day of July, 2011, and that the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
	Cleaned out with a 10" bit to 1,128 feet deep. Hit a lot of junk. Put on a power swivel. Cleaned out with an 8" flat bottom mill to 1,318' deep.			
	Logged the hole with Century Wireline Service. The bottom of the Pittsburgh coal seam is 1,099'. The hole deviated 36.3 feet at the coal seam. Based on the logs, there is no pipe in the coal seam.			
	There is a 328' thick bottom plug made of expanding cement from 1,318' to 990' feet.			
	The rest of the hole was filled with regular cement from 990' to the surface.			


Description of monument: 4 1/2" Pipe with metal plate, API #, and date plugged and that the work of plugging and filling said well was completed on the 28th day of December, 2011.

And further deponents saith not X Kenneth Gump
Garrett Hickman

Sworn and subscribe before me this 6th day of March, 2012
My commission expires: July 7, 2017

Notary Public

Oil and Gas Inspector: S. E. Ward 3/7/17



RECEIVED
Office of Oil & Gas

JUN 12 2012

WV Department of
Environmental Protection