

Rev (5-01)
WR-38
DATE: 12-23-11

API # 47-6101637P

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Latocha, Michael. Operator Well No.: F2- S23

LOCATION: Elevation: 1,339' Quadrangle: Blacksville
District: Clay County: Monongalia
Latitude: 14.800' Feet South of 39 Deg. 40 Min. 00 Sec.
Longitude: 7.032' Feet West of 80 Deg. 12 Min. 30 Sec.

Well Type: OIL X GAS _____

Company: Eastern Associated Coal LLC Coal Operator: Eastern Associated Coal LLC
1044 Miracle Run Road or Owner 1044 Miracle Run Road
Fairview, WV 26570 Fairview, WV 26570

Agent: Edward Y. Hoy Coal Operator or Owner Office of Oil & Gas

Permit Issued Date: October 19, 2011

JUN 12 2012

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of Monongalia ss:

WV Department of
Environmental Protection

+ Gary C Thomas and Jeff Sine being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well, and Sam Ward, Oil and Gas Inspector representing the Director, say that said work was commenced on the 8th day of November, 2011, and that the well was plugged and filled in the following manner:


TYPE	FROM	TO	PIPE REMOVED	LEFT
	Cleaned out with a 13" bit to 474'. Cleaned out hole with 10" bit to 980'. Cleaned out with 9 5/8" bit to 1,110'.			
	Logged the hole with Century Wireline Service. The bottom of the Pittsburgh coal seam is 899'. The hole deviated 10.0' at the coal seam. There is 7" pipe from the 938' to 1,110' deep. This pipe was ground up with the 9 5/8" bit.			
	There was an expanding cement plug from 1,110 feet deep to 780 feet deep. Then from 780' to the surface, the rest was pumped with regular cement.			
	The plug was pumped by BJ Hughes.			

Description of monument: 4 1/2" Pipe with metal plate, API #, and date plugged and that the work of plugging and filling said well was completed on the 20th day of December, 2011.

And further deponents saith not. x Gary C Thomas

Sworn and subscribe before me this 23rd day of December, 2011

My commission expires: July 7, 2017



[Signature]
Notary Public
[Signature]

06/22/2012