

Rev (5-01)
WV-88
DATE: 05-28-12

API # 47-8101640P

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator, and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Firm name: Albert Kenneth Operator Well No.: F2-529
LOCATION: Elevation: 1,532' Quadrangle: Grant Town
District: Clay County: Monongalia
Latitude: 37° 57' Feet South of 38 Deg. 37 Min. 30 Sec.
Longitude: 79° 21' Feet West of 80 Deg. 12 Min. 30 Sec.
Well Type: OIL X GAS _____
Company: Eastern Associated Coal LLC Coal Operator: Eastern Associated Coal LLC
1044 Miracle Run Road or Owner: 1044 Miracle Run Road
Fairview, WV 26570 Fairview, WV 26570
Agent: Edward Y. Hoy Coal Operator or Owner _____

Permit Issued Date: February 09, 2012

RECEIVED
Office of Oil & Gas

APR 07 2014

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of Monongalia ss:

WV Department of
Environmental Protection

Jeff Sime and Chris Thomas being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well, and Bern Ward, Oil and Gas Inspector representing the Director, say that said work was commenced on the 1st day of May, 2012, and that the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
	Cleaned out with an 1 1/2" bit down to 1170'. Twisted off a joint of drill pipe. Fished it out. Put on a 9 5/8" bit and cleaned out the hole down to 1310'.			
	Logged the hole with Century Wireline Services. The bottom of the Pittsburgh coal seam is 1098'. The hole deviated 7.3 feet at the coal seam. Based on logs, there is no casing in the well bore.			
	There is a 320' thick bottom plug made of expanding cement from 1,310' to 890' feet.			
	The rest of the hole was filled with regular cement from 890' to the surface. The cement was pumped by Allied Oil & Gas Services LLC.			

Description of monument: 4 1/2" Pipe with metal plate, API #, and date plugged and that the work of plugging and filling said well was completed on the 16 day of May, 2012.


And further deponents each not.

Chris Thomas

Sworn and subscribed before me this 28th day of June, 2012
My commission expires: June 7, 2017

Oil and Gas Inspector: _____

Edward Y. Hoy
Notary Public



04/11/2014