

Rev (5-01)
WR-38
DATE: 10-29-12

API # 47-6101649P

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Ellen Curfman Operator Well No.: F2- S42
LOCATION: Elevation: 1,465' Quadrangle: Grant Town
District: Clay County: Monongalia
Latitude: 2,138' Feet South of 39 Deg. 37 Min. 30 Sec.
Longitude: 8,442' Feet West of 80 Deg. 12 Min. 30 Sec.
Well Type: OIL X GAS _____

Company: Eastern Associated Coal LLC Coal Operator: Eastern Associated Coal LLC
1044 Miracle Run Road or Owner 1044 Miracle Run Road
Fairview, WV 26570 Fairview, WV 26570
Agent: Matthew L. Bonnell Coal Operator or Owner _____

RECEIVED
Office of Oil and Gas
JAN 14 2015

Permit Issued Date: September 27, 2012

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of Monongalia ss:


WV Department of
Environmental Protection
WV Department of
Environmental Protection

x Gary C Thomas and x Garrett Hickman being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well, and Sam Ward, Oil and Gas Inspector representing the Director, say that said work was commenced on the 6th day of October, 2012, and that the well was plugged and filled in the following manner:

| TYPE | FROM | TO | PIPE REMOVED | LEFT |
|---|------|----|--------------|------|
| Cleaned out with a 12 1/4" bit down to 948". Then cleaned out with a 7 3/4" bit to 1,717'. Then cleaned out with a 6" bit down to 2,175'. | | | | |
| Logged the hole with Century Wireline Service. The bottom of the Pittsburgh coal seam is 958'. The hole deviated 9.7' feet at the coal seam. Based on logs, there is 8" casing from 980' down to 1840", and 7" casing from 1,902 down to 2,002. | | | | |
| Both strings of pipe were shot every 50 feet by Timco. | | | | |
| The well was plugged by BJ Hughes. There is a bottom hole cement plug from 2,175' up to 1,158'. Then they set an expanding cement plug from 1,158' to 752'. Then from 752' to surface it was filled with cement. | | | | |

Description of monument: 4 1/2" Pipe with metal plate, API #, and date plugged and that the work of plugging and filling said well was completed on the 26th day of October, 2012.

And further deponents saith not Gary C Thomas
Garrett Hickman



Sworn and subscribed before me this 29th day of OCTOBER, 2012
July 7, 2012
Notary Public
Douglas Hays 11-9-12

01/16/2015