

Rev (6-01)
WR-38
DATE: 12-18-13

47-061-01662

API # 47-6101662P

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Chisler, Bruce Operator Well No.: F2-125

LOCATION: Elevation: 1,362' Quadrangle: Blacksville
District: Clay County: Monongalia
Latitude: 6.853 Feet South of 39 Deg. 42 Min. 30 Sec.
Longitude: 7.278 Feet West of 80 Deg. 12 Min. 30 Sec.
Well Type: OIL X GAS

Company: Eastern Associated Coal LLC Coal Operator: Eastern Associated Coal LLC
1044 Miracle Run Road or Owner 1044 Miracle Run Road
Fairview, WV 26570 Fairview, WV 26570

Agent: Matthew L. Bonnell Coal Operator or Owner

Permit Issued Date: July 26, 2013

AFFIDAVIT

RECEIVED
Office of Oil & Gas

STATE OF WEST VIRGINIA,
County of Monongalia ss:

MAR 31 2014

*Gary C Thomas and *Bruce A Chisler and John Shockey of the Department of Environmental Protection according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well, and John Shockey, Oil and Gas Inspector representing the Director, say that said work was commenced on the 23rd day of October, 2013, and that the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Drilled with a 12 1/2" bit down to 1,050'. Cleansed out with a 6 1/2" cone bit to 1,780'.				
Ran logs with Century Wireline Services. Based on the logs the Pittsburgh coal seam is 1,012'-1,019'. The well deviated 17.4' at the coal seam. There was no casing in the coal seam.				
There is a bottom hole cement plug from 1,780 up to 1,230'. Then they set an expanding cement plug from 1,230 to 800'. Then from 800' to surface it was filled with cement.				
There were 785 sacks of Portland and 105 sacks of expanding cement used to plug the well.				


Description of monument: 4 1/2" Pipe with metal plate, API #, and date plugged and that the work of plugging and filling said well was completed on the 4th day of December 2013.

And further deponents saith not. *Gary C Thomas
*Bruce A Chisler

Sworn and subscribe before me this 18th day of December, 2013
My commission expires: July 7, 2017

Oil and Gas Inspector: John Shockey

Notary Public



04/04/2014