

STATE OF WEST VIRGINIA  
DEPARTMENT OF ENVIRONMENTAL PROTECTION  
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: B. F. Liming Operator Well No.: 8240

LOCATION: Elevation: 1381' Quadrangle: Hundred W.VA, PA  
District: Battelle County: Monongalia  
Latitude: \_\_\_\_\_ Feet South of 39 Deg. 39 Min. 30.84 Sec.  
Longitude: \_\_\_\_\_ Feet West of -80 Deg. 23 Min. 57.32 Sec.

Well Type: OIL \_\_\_\_\_ GAS X

Company West Virginia Land Resources Inc. Coal Operator West Virginia Land Resources Inc.  
1 Bridge Street or Owner 1 Bridge Street  
Monongah, WV 26554 Monongah, WV 26554  
Agent David Roddy Coal Operator \_\_\_\_\_  
or Owner \_\_\_\_\_  
Permit Issued Date 12/22/2021

AFFIDAVIT


STATE OF WEST VIRGINIA,  
County of Monongalia ss:

Matthew A. Yearsley and Kevin S. Wright being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 6th day of June, 2022, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Thixotropic w/ Green Dye and Gas Block	1506'	1009'		
Expandable Cement	1009'	Surface		
8 5/8" Casing	1417'	Unknown	357'	Unknown
16" Conductor	Surface	20'	0'	20'

Description of monument: 77" of 7" casing with company name, well #, API#, and date cemented and that the work of plugging and filling said well was completed on the 24th day of June, 2022.

And further deponents saith not. Matthew A. Yearsley  
Kevin S. Wright



Sworn and subscribe before me this 8 day of August, 2022

My commission expires: June 8, 2027

Christopher Andrew Willis  
Notary Public

Affidavit reviewed by the Office of Oil and Gas: \_\_\_\_\_ Title: \_\_\_\_\_

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES INC  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address

WEST VIRGINIA LAND RESOURCES INC  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address  
KYLIE D. BARNHART  
Lease or Property Owner  
95 PONE RD. BURTON, WV 26562  
Address

WEST VIRGINIA LAND RESOURCES INC  
Name of Well Operator  
1 BRIDGE STREET MONONGAH, WV 26554  
Complete Address  
HUNDRED W.VA, PA  
Well Location  
BATTELLE  
District  
MONONGALIA  
County  
8240  
Well No.  
B.F. LIMING  
Farm

STATE INSPECTOR SUPERVISING PLUGGING \_\_\_\_\_

AFFIDAVIT

STATE OF WEST VIRGINIA,  
County of MONONGALIA ss:  
MATTHEW A. YEARSLEY and KEVIN S. WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources Inc. well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 6<sup>th</sup> day of June, 2022 and that the well was plugged in the following manner:

Sand or Zone Record	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Formation				
	Cleaned a 12 1/4" hole from the surface to 320'. Reduced the hole to 9 7/8" at 320'. Cleaned a 9 7/8" hole from 320' to the top of the existing 8 5/8" casing at 1060'. Reduced the hole to a 6 1/4" bit and cleaned out 8 5/8" casing from 1060' to 1506'. Removed 357' of 8 5/8" casing from 1060' to 1417'. Left an unknown amount of 8 5/8" casing in the hole from 1417' to an unknown depth. Cleaned a 9 7/8" hole from 1060' to 1417'. Cleaned 9 7/8" hole through the Pittsburgh Coal Seam (1209' to 1217'). Left 20' of 16" conductor in the hole from the surface to 20'. <b>Cemented the hole from 1506' to the surface as follows:</b> From 1506' to 1009' with 260 sacks of Thixotropic Cement with Green Dye and a Gas Blocker additive. Tagged top of Thixotropic cement plug at 1009'. Cemented the hole from 1009' to the surface with 515 sacks of Expandable Cement. Cement did circulate. A total of 775 sacks of cement were used to fill the hole from 1506' to the surface.	8 5/8" Casing 16" Conductor	357' 0'	Unknown 20'
Coal Seams		Description of Monument		
<u>Pittsburgh</u>	1209' – 1217'	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 24<sup>th</sup> day of June, 2022

And further deponents saith not.

Matthew A. Yearsley  
Matthew A. Yearsley

Kevin S. Wright  
Kevin S. Wright

Sworn to and subscribed before me this 8 day of August 2022

[Signature]  
Notary Public

My commission expires: June 8, 2027

Permit No. 47-061-01897  
Well No. 8240  
Latitude: 39° 39' 30.84"N  
Longitude: -80° 23' 57.32"W

