

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Mary C. Poe Hrs. Operator Well No.: 8192

LOCATION: Elevation: 1200.00' Quadrangle: Hundred WV, PA
District: Battelle County: Monongalia
Latitude: _____ Feet South of 39 Deg. 39 Min. 28.96 Sec.
Longitude: _____ Feet West of -80 Deg. 23 Min. 45.04 Sec.

Well Type: OIL _____ GAS X

Company West Virginia Land Resources, Inc. Coal Operator West Virginia Land Resources, Inc.
1 Bridge Street or Owner 1 Bridge Street
Monongah, WV 26554 Monongah, WV 26554
Coal Operator _____
Agent David Roddy or Owner _____
Permit Issued Date 12/21/2022

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of Monongalia ss:

Matthew A. Yearsley and Kevin S. Wright being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 29th day of March, 2022, and the well was plugged and filled in the following manner:


TYPE	FROM	TO	PIPE REMOVED	LEFT
Thixotropic w/ Green Dye and Gas Block	1306'	809'		
Expandable Cement	809'	Surface		
8 5/8" Casing	1167'	1242'	271'	75'
16" Conductor	Surface	20'	0'	20'

RECEIVED
Office of Oil and Gas
JUN 24 2022

Description of monument: 77" of 7" casing with company name, well #, API #, and date cemented and that the work of plugging and filling said well was completed on the 21st day of April, 2022.

WV Department of
Environmental Protection

And further deponents saith not. Matthew A. Yearsley
Kevin S. Wright



Sworn and subscribe before me this 9th day of May, 2022

My commission expires: 09/15/22
[Signature]
Notary Public

Affidavit reviewed by the Office of Oil and Gas: Kenneth Greynolds Title: _____

JUN 24 2022

02/23/2024
WV Department of
Environmental Protection

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

RECEIVED
Office of Oil and Gas
JUN 24 2022
WV Department of
Environmental Protection

WEST VIRGINIA LAND RESOURCES, INC.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
WEST VIRGINIA LAND RESOURCES, INC.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
JOHN II & TRACEY L. PETERS
Lease or Property Owner
P.O. BOX 15 HUNDRED, WV 26575
Address

WEST VIRGINIA LAND RESOURCES, INC.
Name of Well Operator
1 BRIDGE STREET MONONGAH, WV 26554
Complete Address
HUNDRED W.VA, PA
Well Location
BATTELLE
District
MONONGALIA
County
8192
Well No.
MARY C. POE HRS.
Farm

STATE INSPECTOR SUPERVISING PLUGGING Kenneth Greynolds
Digitally signed by Kenneth Greynolds
DN: CN = Kenneth Greynolds, email = Kenneth.L.Greynolds@wv.gov C = AD O =
WVDEP OU = Oil and Gas
Date: 2022.05.11 09:36:57 -0400


AFFIDAVIT

STATE OF WEST VIRGINIA,
County of MONONGALIA ss:
MATTHEW A. YEARSLEY and KEVIN S. WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources, Inc. well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 29th day of March, 2022 and that the well was plugged in the following manner:

Sand or Zone Record	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Formation				
Cleaned the hole with a 12 1/4" bit from the surface to 222'. Reduced the hole to 9 7/8" at 222'. Cleaned the hole with a 9 7/8" bit from 222' to the top of the existing 8 5/8" casing at 896'. Reduced the hole to 7 7/8" at 896'. Cleaned the hole with a 7 7/8" bit from 896' to 1306'. Removed 271' of 8 5/8" casing from 896' to 1167'. Left 75' of 8 5/8" casing in the hole from 1167' to 1242'. Attempted to remove remaining 8 5/8" casing by pulling 150% of the string weight but all attempts were unsuccessful. Cut remaining 8 5/8" casing at 1187'. Cleaned a 9 7/8" hole through the Pittsburgh Coal Seam (1079.9' - 1086.7'). Left 20' of 16" conductor pipe in the hole from the surface to 20'.	8 5/8" Casing 16" Conductor	271' 0'	75' 20'	
Cemented the hole from 1306' to surface as follows:				
From 1306' to 809' with 210 sacks of Thixotropic Cement with Green Dye and a gas blocker additive. Tagged the top of the Thixotropic plug at 809'. Cemented the hole from the top of the Thixotropic cement plug at 809' to the surface with 480 sacks of Expandable Cement. Cement did circulate at the surface. A total 690 sacks of cement were used to fill the hole from 1306' to the surface.				
Coal Seams		Description of Monument		
<u>Pittsburgh</u>	<u>1079.9' - 1086.7'</u>	<u>77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.</u>		

... and that the work of plugging and filling said well was completed on the 21st day of April, 2022

And further deponents saith not.



Matthew A. Yearsley
Matthew A. Yearsley

Kevin S. Wright
Kevin S. Wright

Sworn to and subscribed before me this 9th day of May, 2022

[Signature]
Notary Public

My commission expires: 09/15/22

Permit No. 47-061-01898
Well No. 8192
Latitude: 39° 39' 28.96"N
Longitude: -80° 23' 45.04"W