

STATE OF WEST VIRGINIA  
DEPARTMENT OF ENVIRONMENTAL PROTECTION  
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: J. Liming Operator Well No.: 8239

LOCATION: Elevation: 1391' Quadrangle: Hundred W.VA, PA  
District: Battelle County: Monongalia  
Latitude: \_\_\_\_\_ Feet South of 39 Deg. 39 Min. 42.37 Sec.  
Longitude: \_\_\_\_\_ Feet West of -80 Deg. 23 Min. 17.27 Sec.

Well Type: OIL \_\_\_\_\_ GAS X

Company West Virginia Land Resources, Inc. Coal Operator West Virginia Land Resources, Inc.  
1 Bridge Street or Owner 1 Bridge Street  
Monongah, WV 26554 Monongah, WV 26554  
Agent David Roddy Coal Operator \_\_\_\_\_  
Permit Issued Date 09/06/2022 or Owner \_\_\_\_\_

AFFIDAVIT


STATE OF WEST VIRGINIA,  
County of Monongalia ss:

Matthew A. Yearsley and Kevin S. Wright being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 13th day of March, 2023, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Thixotropic w/ Green Dye and Gas Block	1468'	1178'	16" Conductor - 0'	20'
Thixotropic Cement w/ Green Dye	1178'	1036'		
1036'	Surface			

Description of monument: 77" of 7" casing with company name, well #, API #, and date cemented and that the work of plugging and filling said well was completed on the 29th day of March, 2023.

And further deponents saith not. Matthew A. Yearsley  
Kevin S. Wright



Sworn and subscribe before me this 24 day of April, 2023

My commission expires: June 8, 2027  
Christopher Willis  
Notary Public

Affidavit reviewed by the Office of Oil and Gas: \_\_\_\_\_ Title: Inspector

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES INC  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address  
WEST VIRGINIA LAND RESOURCES INC  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address  
CAROL A. & KENNETH SENCAJ  
Lease or Property Owner  
1745 LAKE AVE. WHITING, IN 46394  
Address

WEST VIRGINIA LAND RESOURCES INC  
Name of Well Operator  
1 BRIDGE STREET MONONGAH, WV 26554  
Complete Address  
HUNDRED W.VA, PA  
Well Location  
BATTELLE  
District  
MONONGALIA  
County  
8239  
Well No.  
J. LIMING  
Farm

STATE INSPECTOR SUPERVISING PLUGGING \_\_\_\_\_

AFFIDAVIT

STATE OF WEST VIRGINIA,  
County of MONONGALIA ss:

MATTHEW A. YEARSLEY and KEVIN S. WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources Inc. well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 13<sup>th</sup> day of March, 2023 and that the well was plugged in the following manner:

Sand or Zone Record Formation	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
	Cleaned a 12 1/4" hole from the surface to 300'. Cleaned a 9 7/8" hole from 300' to 1329'. Cleaned a 7 7/8" hole from 1329' to 1468'. Cleaned a 9 7/8" hole through the Pittsburgh Coal Seam (1236.9' – 1243.0'). Left 20' of 16" conductor pipe in the hole from the surface to 20'.  <b>Cemented the hole from 1468' to the surface as follows:</b> From 1468' to 1036' with 235 sacks of Thixotropic Cement with Green Dye and a Gas Blocker additive. Tagged top of Thixotropic Cement plug at 1178'. Cemented the hole from 1178' to the surface with 20 sacks of Thixotropic Cement with Green Dye and 585 sacks of Expandable Cement. Cement did circulate at the surface. A total of 840 sacks of cement were used to fill the hole from 1468' to the surface.	16" Conductor	0'	20'
<b>Coal Seams</b>		<b>Description of Monument</b>		
<u>Pittsburgh</u>	1236.9' – 1243.0'	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 29<sup>th</sup> day of March, 2023

And further deponents saith not.

Matthew A. Yearsley  
Matthew A. Yearsley


Kevin S. Wright  
Kevin S. Wright

Sworn to and subscribed before me this 24 day of April, 2023

[Signature]  
Notary Public

My commission expires:

June 8, 2027



Permit No. 47-061-01913  
Well No. 8239  
Latitude: 39° 39' 42.37"N  
Longitude: -80° 23' 17.27"W