

STATE OF WEST VIRGINIA  
DEPARTMENT OF ENVIRONMENTAL PROTECTION  
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: T.J. Dawson Operator Well No.: 8136

LOCATION: Elevation: 1,387.80' Quadrangle: Hundred, W.VA, PA  
District: Battelle County: Monongalia  
Latitude: 39.66469 Feet South of 39 Deg. 39 Min. 52.90 Sec.  
Longitude: -80.40089 Feet West of -80 Deg. 24 Min. 03.22 Sec.

Well Type: OIL \_\_\_\_\_ GAS X

Company West Virginia Land Resources, INC. Coal Operator West Virginia Land Resources, INC.  
1 Bridge Street or Owner 1 Bridge Street  
Monongah, WV 26554 Monongah, WV 26554  
Agent David Roddy Coal Operator \_\_\_\_\_  
Permit Issued Date 1/22/24 or Owner \_\_\_\_\_

AFFIDAVIT


STATE OF WEST VIRGINIA,  
County of Monongalia ss:

Mathew Yearsly and John Campbell being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 22nd day of February, 2024, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Thixotropic w/ Green Dye and Gas Blocker	1462'	1002'	16" Conductor Casing 0'	20'
Expandable	1002'	Surface		

Description of monument: 77" of 7" casing with company name, well #, API #, and date completed and that the work of plugging and filling said well was completed on the 8th day of March, 2024.

And further deponents saith not. Matthew A. Yearsley  
John Campbell



Sworn and subscribe before me this 14th day of March, 2024

My commission expires: June 8, 2027  
Christopher Willis  
Notary Public

Affidavit reviewed by the Office of Oil and Gas: \_\_\_\_\_ Title: Inspector

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES. INC.  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address  
WEST VIRGINIA LAND RESOURCES. INC  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address  
COLUMBIA GAS TRANSMISSION CORP.  
Lease or Property Owner  
PO BOX 498 Washington, PA 15301  
Address

WEST VIRGINIA LAND RESOURCES. INC  
Name of Well Operator  
1 BRIDGE STREET MONONGAH, WV 26554  
Complete Address  
HUNDRED W.VA, PA  
Well Location  
BATTELLE  
District  
MONONGALIA  
County  
8136  
Well No.  
T.J.DAWSON  
Farm

STATE INSPECTOR SUPERVISING PLUGGING Gayne Knitowski

AFFIDAVIT

STATE OF WEST VIRGINIA,  
County of MONONGALIA ss:  
MATTHEW A. YEARSLEY and JOHN CAMPBELL being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources, INC. well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 22<sup>nd</sup> day of February, 2024 and that the well was plugged in the following manner:

Sand or Zone Record Formation	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
	Cleaned 12 1/4" hole from surface to 278'. Reduced to 9 7/8" at 278'. Cleaned 9 7/8" from 278' to bottom at 1462'. Cleaned 9 7/8" hole through the Pittsburgh Coal seam (1202.2' - 1209'). Left 20' of 16" conductor casing in the hole from 20' to surface.  <u>Cemented Hole from 1462' to surface as follows:</u>  Cemented bottom hole from 1462' to 1002' using 305 sacks of Thixotropic Cement with Green Dye and Gas Blocker additive. Cemented from 1002' to surface using 720 sacks of Expandable Cement. Cement did circulate at the surface. A total of 1025 sacks of cement were used to fill hole from 1462' to surface.	16" Conductor Casing	0'	20'
<u>Coal Seams</u>		<u>Description of Monument</u>		
<u>Pittsburgh</u>	1202.2' - 1209'	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 8<sup>th</sup> day of March, 2024

And further deponents saith not.


Matthew A. Yearsley  
Matthew A. Yearsley

John Campbell  
John Campbell

Sworn to and subscribed before me this 14<sup>th</sup> day of March, 2024

[Signature]  
Notary Public

My commission expires:  
June 8, 2027



Permit No. 47-061-01954  
Well No. 8136  
Latitude: 39° 39' 49.3236"N  
Longitude: -80° 24' 3.8736"W